

**SURVEY &
REMONUMENTATION**

AUG 08 1897

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49NR48W	E- 12
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received for record the
11th day of JUNE

A. D. 1997 at 10:35 o'clock

A m., and recorded in
Liber 6 of CORNERS

on page 141
Colleen M. Kischak, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 cor. comm. to sec's 32 & 33

I, John P. Goss, in a field survey on May 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Ives on August 8, 1848. Set post.
Original bearing trees: Y. Birch 16" S 44° E 37 links
Hemlock 12" N 42° W 14 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence of the corner position could be found due to road construction.
Found 1/2 inch rebar 2 inches below asphalt in intersection of Lake and Brace Road. I accepted this as corner position. It has been used in many surveys and is generally accepted as the 1/4 corner. I updated the corner monument and accessories as noted below to state and county specification. Act 74 research on file.

PEER GROUP APPROVED
Richard P. Dahn 6/10/97
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I drove the 1/2" rebar down and over it I place a 2 1/2" brass cap with a 2" stem, 1 1/2" below surface of asphalt. Cap is stamped T.49 N., R.48 W.; 1/4; S-32, S-33, 1997; P.S. 23509. I established the following bearing trees and reference objects.

9" White Birch S 43° E 42.95'
22" Maple N 24° W 85.63'
P.Pole #32-94/48 S 37° W 59.47'
Reference Monument consisting of 2 1/2" x 30" aluminum monument with a 3/4" aluminum cap stamped to indicate corner position.

N 53° E - 35.51', with 6' rail & sign - 1.1'

Signed by John P. Goss Date May 17, 1997

Surveyor's Michigan License No. 23509

Fed. No. X - 9

