

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
19TH day of AUGUST

A. D. 1994 at 1:10 o'clock
P m., and recorded in

Liber 5 of CORNERS
 on page 72

Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

GOGEBIC
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>49</u> R <u>48</u> | <u>G-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Earl W. Applekamp, in a field survey on May 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the regulations of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	6	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, August 7, 1848.

Original bearing trees:

Hemlock	24"	S89°E	32 links
Hemlock	6"	S78°W	30 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a squared Cedar post at the corner position. Mr. Tom Erickson, a 76 year old lifelong resident of the area testified this post and another before had always been at this location. His father had showed him the corner at a young age. I found the remains of two Hemlock bearing trees at the recorded bearing and distance from the post. I accepted the post as marking the original corner position based on the two bearing tree remains and the testimony of Mr. Tom Erickson. I monumented the corner to state and county specifications as noted below.

PEER GROUP

Approved

Richard P. Deahn

8/17/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2 1/2" x 30" long split base aluminum monument with a 3 1/4" aluminum cap stamped to read: County Monumentation, 1/4, S-33, S-34, T49N R48W, 1994 P.S. 17610. I established the following reference trees and objects.

Steel Sign Post	S78°E	2.18 feet	7" Maple	N30°E	10.51 feet
7" Maple	S60°W	19.75 feet	7" Maple	S38°E	13.84 feet

Signed by Earl W. Applekamp

Date August 10, 1994

Surveyor's Michigan License No. 17610