

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
16th day of AUGUST
A. D. 1996 at 2:30 o'clock
P. M., and recorded in
Liber 6 of CORNERS

on page 41
Richard J. Brown
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 50NR 45W C-10
T R
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

1/4 cor. comm. to sec's. 29 & 30

I, John P. GOSS, in a field survey on Sept. 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column C and row 10.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt on July 26, 1848. Set Hemlock post.
Original bearing trees: Hemlock 18" S 30° W 4 links
Hemlock 14" N 18° E 31 links
Keith Sackett, R.L.S. of D.N.R. on July 20, 1980 found 30" hemlock stump N 20° E @ 20.7'. He set a 1" iron pipe with 4" aluminum cap stamped to noted corner location. He recorded said corner in Liber 2 on page 122 of Land Corners for Gogebic County, with the following bearing trees: 30" Hemlock- S 30° W- 3.4', 1/4 S, NBT; 10" Maple- East- 11.5', 1/4 S, NBT; 6" Maple- N 03° W- 42.2', 1/4 S, NBT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found the 1" iron pipe with 4" aluminum cap stamped to noted corner location and it checked with K. Sackett witnesses on his certification. I updated the corner accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard L. Wrahn 9/12/96
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the 1" iron pipe with 4" aluminum cap stamped to note corner location. I established the following existing and new bearing trees and reference objects.

- (1) 30" Hemlock (stump) S 30° W., 3.4', 1/4 S, NBT
(2) 12" Maple (dead) East 11.5', 1/4 S, NBT
(3) 9" Maple N 03° W 42.55', 1/4 S, NBT
(4) 9" Hemlock S 73° W 33.41'
(5) 17" Y. Birch S 52° E 18.00'
(6) 6' Rail & sign N 40° E 1.15'

Note: No. 1 & 2 measure to face of tree.

Signed by John P. Goss Date Sept 1, 1996

Surveyor's Michigan License No. 23509

Fed. No. T-5

