

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	GOGEBIC COUNTY LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. R. 45 E.	A-13, B-13, C-13
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 31, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A-13: Found 2" I.D. iron pipe with cap marked $\frac{36}{1} \frac{31}{6}$ 1959 TWN Post T49,50N, R45,46W

Corner B-13: Found 2" I.D. iron pipe with cap marked $\frac{1}{4} \frac{31}{6}$ T50N, R45W 1959 TWN T49N, R45W

Corner C-13: Found 2" I.D. iron pipe with cap marked $\frac{31}{6} \frac{32}{5}$ 1959 TWN T49,50N, R45W

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A-13: Restored at pipe.
 Corner B-13: Restored at pipe.
 Corner C-13: Restored at pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A-13: 2" I.D. iron pipe with cap.
 8" Ash S66W 23.7 ft., S1, NBT
 2" W. Birch S78E 22.6 ft., S6, NBT
 5" Maple N29W 29.7 ft., S36, NBT

Corner B13: 2" I.D. iron pipe with cap.
 4" Sugar N60E 25.1 ft., 1/4S, NBT
 3" Sugar N69W 33.6 ft., 1/4S, NBT
 7" W. Birch S51E 29.1 ft., 1/4S, NBT

Corner C-13: 2" I.D. iron pipe with cap.
 8" Y. Birch S18E 21.0 ft., S 5, NBT
 5" Maple S85W 15.7 ft., S 6, NBT
 6" Ash N63E 26.3 ft., S32, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 9-3-80
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
 REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET