

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

GOGEBIC COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> ^{N.} S. , R. <u>45</u> ^{E.} W.	<u>C-10</u>
2. PROPERTY CONTROLLING IN SECTION <u>30</u>	T. <u>50</u> ^{N.} S. , R. <u>45</u> ^{E.} W.	<u>11</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, R. _____, S. _____, E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 11: Not set on original survey nor subsequently, apparently.

Corner C-10: Found 30" Hemlock Stub N20E 20.7 ft., believed to be original bearing tree. Stub has old face but is too deteriorated to identify scribing. Stub has forest service location poster dated 1935.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 11: Established 08/04/80 during section subdivision.

Corner C-10: Restored 07/21/80 from hemlock stub.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 11: Set 1" I.D. x 30" iron pipe with 4" aluminum cap.
 4" Sugar N02E 17.2 ft., 1/16S, BT
 2" Y. Birch S43E 9.0 ft., 1/16S, BT
 5" W. Birch S57W 5.9 ft., 1/16S, BT

Corner C-10: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 30" Hemlock S30W 3.4 ft., 1/4S, NBT
 10" Maple East 11.5 ft., 1/4S, NBT
 6" Maple N 3W 42.2 ft., 1/4S, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 9-3-80
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

