

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

GOGEBIC COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. R. 45 <input checked="" type="checkbox"/> W.	A-12
2. PROPERTY CONTROLLING IN SECTION	31 T. 50 N. R. 45 <input checked="" type="checkbox"/> W.	8
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 5, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A-12: Found 1" I.D. x unknown length iron pipe set from possible bearing tree by W. S. Bromley. Pipe fits good with land calls.

Corner 8: Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A-12: Restored at iron pipe.

Corner 8: Established during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A-12: 1" I.D. by unknown length iron pipe.
 4" Maple S25W 21.5 ft., 1/4S, NBT
 4" Maple N33E 33.3 ft., 1/4S, NBT
 5" Ash N33W 40.8 ft., 1/4S, NBT

Corner 8: Set 1" I.D. x 30" iron pipe with 4" aluminum cap.
 3" Sugar N59W 8.8 ft., 1/16S, BT
 4" Sugar N50E 30.1 ft., 1/16S, BT
 4" Sugar S82E 35.5 ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 7-3-80

MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

