

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(GOGEBIC COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 50 N. R. 45 E. W.	C-12
2. PROPERTY CONTROLLING IN SECTION_____	T. 50 N. R. 45 E. W.	10
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 29, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C-12: Found possible original bearing tree (Sugar 12" N88W 28 links). This tree is now 28" Sugar. Has old scars but is grown in too much for positive I.D. Many old blazes in area.

Corner 10: Found 1" I.D. iron pipe reported to have been set by W. S. Bromley. Fits good with other corners.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C-12: Restored from possible bearing tree.

Corner 10: Restored at 1" pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C-12: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
 7" Hemlock S20E 13.4 ft., 1/4S, NBT
 32" Sugar N15E 10.3 ft., 1/4S, NBT
 28" Sugar N88W 17.6 ft., 1/4S, NBT

Corner 10: 1" I.D. by unknown length iron pipe.
 4" Sugar S12W 25.5 ft., 1/16S, BT
 4" Sugar N40E 28.6 ft., 1/16S, BT
 7" W. Birch N75W 17.6 ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO: _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 9-3-80

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

