

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(GOGEBIC COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. R. 45 E.	C-11
2. PROPERTY CONTROLLING IN SECTION 30	T. 50 N. R. 45 E.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 29, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C-11: Original monument and accessories not found. Found possible original bearing tree, but unable to verify. Falls at intersection of old blazed lines north, south, east, west. Fits good with land calls and other corners.

Corner 15: Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C-11: Restored at possible bearing tree and by land calls.

Corner 15: Established on line and by proportion between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C-11: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.

7" Sugar N 7E 10.2 ft., S29, NBT

5" Sugar S55E 8.7 ft., S32, NBT

14" Sugar S40W 11.2 ft., S31, NBT

Corner 15: Set 1" I.D. x 30" iron pipe.

5" Sugar N36E 19.6 ft., 1/16S, BT

3" Sugar S81E 4.9 ft., 1/16S, BT

8" W. Birch S36W 1.4 ft., 1/16S, BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 9-3-80

MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

