

JAN 20 2000

MONTCALM COUNTY REMONUMENTATION PROGRAM

LIBER 619 PAGE 933

LAND CORNER RECORDATION CERTIFICATE

STATE OF MICHIGAN
GRATIOT COUNTY
RECORDED

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

11 JAN 2000 9:36 A.M.

JANET M. DAVIS
REGISTER OF DEEDS

For corners in
Gratiot
(County)

Located In: Elba Township

Corner Code #

1. Public Land Survey	Sec. 13 T 9N R 1N	K6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William G. Tingley, in a field survey on July 28 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1831, R. Thomas, Deputy Surveyor, G.L.O. Notes North between sections 13 and 14 Set-14 Sec. post
Birch 8 S65 E15
Elm 8 N68 W 12
 - 1997 Gratiot County Road Plans for Mason Road show a 20mm iron pipe in monument box.
 - Found no further evidence

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Excavated 2' x 3.5' deep hole, found 1"OD x 8" long galvanized iron pipe 0.3' below surface, .0.5' west and 0.5' south of witnesses for 1" pipe.
 - Found 3/4" OD x 1.5' long iron pipe 1.1' below road surface, found nothing below 3/4" iron pipe.
 - Corner in line with occupation field/tree line to the west. Distance to K-05 to the north 2656.88 feet and distance to K-07 so south 2656.47 feet.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation monument in place of 3/4" iron pipe

Set nail and tag NW side 24" cottonwood	S68°W	71.55 feet
Set nail and tag SE side 12" cottonwood	S80°W	84.72 feet
Set nail and tag NW side power pole	N18°E	135.70 feet
Centerline of Mason Road	West	3.20 feet

ACCEPTED BY THE GRATIOT COUNTY SURVEYOR GROUP AS THE OFFICIAL CORNER UNDER PUBLIC ACT 345 OF 1990 AT A MEETING HELD 1/20/00

W. G. Tingley
William Tingley, PS, Chairman

This corner is accepted as the best available evidence of the position of the original corner.

Signed by William G. Tingley Date 12/30/99
Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 21, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1992

