

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION GRATIOT (County)

Located In: Corner Code #

STATE OF MICHIGAN GRATIOT COUNTY RECORDED

22 JUL 99 11:51 A.M.

JANET M. DAVIS REGISTER OF DEEDS

WASHINGTON TWP.

Table with 3 columns: Item description, Survey type (T, S), and Corner Code # (C-3).

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Contains numbers 1-36.

I, DAVID R. LOHR, in a field survey on MARCH 23, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. CORNER SET BY AUSTIN BURT, DEPUTY SURVEYOR, IN MAY 1852. "S 5 E - CORRECTED BETWEEN SECS. 5 + 6." "OLD CORNER OF SECTIONS 5-6-7&8" WITNESSED BY: BEECH 12 S 40 1/2 W, 30 L (19.80') ELM 8 N 53 E, 43 L (28.38')
2. CORNER REFERENCED IN SURVEY BY R.J. FRAKER, COUNTY SURVEYOR, DATED MAY 1867 ON PAGE 120 OF "SURVEY FIELD BOOKS - T9N, R2W" ON FILE AT GRATIOT COUNTY REGISTER OF DEEDS. "SEE SEC. 6" SURVEY SHOWS DISTANCE EAST OF 39.76 CH. (2624.16') AND SOUTH OF 40.10 CH. (2646.60')
3. CORNER REFERENCED IN SURVEY BY D.W.A (DANIEL W. ALTENBURG), COUNTY SURVEYOR, DATED OCT. 1876 ON PAGE 116 OF "SURVEY FIELD BOOKS - T9N, R2W" ON FILE AT GRATIOT COUNTY REGISTER OF DEEDS. "POST 3 X 3, OCF" WITNESSED BY: ELM 8", N 55 3/4 W, 1.51 (99.66'), S. OAK 3", N 25 W, 1.36(89.76'). SURVEY SHOWS DISTANCE NORTH OF 40.02 CH. (2641.32') AND WEST OF 40.04 CH.(2642.64'). MARGINAL NOTE (NOT DATED), "X" POST 4 X 4, 2 STONES, ELM 8", N 60 1/2 W, .87 (57.42'), ELM 8" N65 E, .94 (62.04')
4. CORNER REFERENCED IN SURVEY BY R.J. FRAKER, COUNTY SURVEYOR, DATED DEC. 1877 ON PAGE 118 OF "SURVEY FIELD BOOKS - T9N, R2W" ON FILE AT GRATIOT COUNTY REGISTER OF DEEDS. "SEE SEC. 6, W. ASH 10", S 33 1/4 W, 1.71 (112.86') SURVEY SHOWS DISTANCE SOUTH OF 40.08 CH. (2645.28') AND DISTANCE WEST 40.04 CH.(2642.64')
5. CORNER REFERENCED IN SURVEY BY R.J. FRAKER, COUNTY SURVEYOR, DATED DEC. 1877 ON PAGE 114 OF "SURVEY FIELD BOOKS - T9N, R2W" ON FILE AT GRATIOT COUNTY REGISTER OF DEEDS. "SEE SEC. 6" SURVEY SHOWS DISTANCE NORTH OF 40.04 CH. (2642.64') AND DISTANCE EAST 39.83 CH. (2628.78')

SEE BACK OF SHEET:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 3/4"(19mm)PIPE, 0.4'(0.12m) BELOW GRAVEL SURFACE. EXCAVATED AREA 4 FT. (1.22m) X 4 FT. (1.22m) X 3 FT.(0.914m) DEEP AROUND PIPE, FOUND PIPE TO BE DRIVEN INTO ANCIENT 3"(75mm) SQUARE POINTED CEDAR POST WITH LARGE STONE ON NORTH SIDE. FOUND MSHD 1953 WITNESS TREE TO NORTHEAST. ACCEPTED PIPE/ CEDAR POST AS CORNER AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. SET STANDARD GRATIOT COUNTY REMONUMENTATION PIPE WITH CAP OVER TOP OF PIPE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

C-3: TOWN 9 NORTH, RANGE 2 WEST, WASHINGTON TOWNSHIP, GRATIOT COUNTY. FOUND PIPE IN 3"(75mm)SQUARE CEDAR POST, WITH STONE. SET STANDARD GRATIOT COUNTY REMONUMENTATION PIPE WITH CAP OVER TOP OF FOUND 3/4" PIPE. WITNESSED BY: SET N&T #30090, SE/S 44"(1.10m)OAK, N 25° E, 94.95' (28.941m) SET N&T #30090, NW/S 6"(.0.15m) POST, N 47° E, 48.99' (14.932m) SET #4 REBAR/CAP #30090, S 76° W, 56.13' (17.109m) TOP/CENTER OF TELEPHONE PED., S 42° E, 52.32' (15.947m) TRAV. PT. #1043(#4 REBAR), N 10° W, 25.04' ( 7.632m) BEARINGS GIVEN ARE MAGNETIC. STANDARD MONUMENTATION CONSISTS OF A BERNTSEN STAINLESS STEEL 30"(762mm)X 2 3/8"(0.65mm)PIPE WITH A BRASS CAP STAMPED "GRATIOT COUNTY REMONUMENTATION", P.S. #30090.

Signed by David R. Lohr Date 7/19/99

Surveyor's Michigan License No. 30090



LIBER 3 PAGE 126

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 7/19/99

William Tingley, PS, Chairman

C-3: WASHINGTON TOWNSHIP, PART A: CONTINUED:

6. CORNER REFERENCED BY MSHD, DATED 11/25/53 BY J. DYKSTRA, SURVEY CHIEF, IN BOOK #5, "SECTION CORNER TIES" PROJECT M29-25. "SEC. COR. COMMON TO SEC'S. 5, 6, 7, 88, T9N, R2W, FOUND OLD STAKE SURROUNDED BY LARGE STONES, BURIED. DROVE 3' OF 1" IRON BAR INTO OLD STAKE - TOP BURIED 8". WITNESSED BY:

- a. APPROX. 2 1/2' W. & 5' N OF CENTER OF INTERSECTION, GRAVEL ROADS.
- b. REF. TAG IN TEL. POLE, N 38° W, 39.07' (GONE)
- c. REF. TAG IN 30' OAK, N 20° E, 95.31' (FOUND)
- d. REF. TAG IN 12" ELM, S 76° E, 136.37' (GONE)
- e. REF. TAG IN 30' B. ASH, S 13° W, 108.14' (GONE)
- f. REF. TAG IN TEL. POLE, S 47° W, 36.44' (GONE)

NOTES SHOW DISTANCE SOUTH OF 2625.82 FEET' (MEASURED 2626.39')

7. NO OTHER REFERENCES FOUND.

LIBER 3 PAGE 127

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

THIS DOCUMENT IS UNCLASSIFIED DATE 11/19/01 BY 60322 UCBAW/STP

PREL.

APR 3 2000

SECTION

SECTION CORNER TIES PROJECT M29-25. "SEC. COR. COMMON TO SEC'S. 5, 6, 7, 88, T9N, R2W, FOUND OLD STAKE SURROUNDED BY LARGE STONES, BURIED. DROVE 3' OF 1" IRON BAR INTO OLD STAKE - TOP BURIED 8". WITNESSED BY:

NOTES SHOW DISTANCE SOUTH OF 2625.82 FEET' (MEASURED 2626.39')

