

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

GRATIOT (County)

Located In:

Corner Code #

WASHINGTON TWP.

1. Public Land Survey	T 9N	R 2W	D-6
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

STATE OF MICHIGAN GRATIOT COUNTY RECORDED

22 JUL 99 11:56 A.M.

JANET M. DAVIS REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I. DAVID R. LOHR, in a field survey on 2/23/99 & 6/25/99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. CORNER NOT SET IN GLO SURVEY.
- 2. CORNER REFERENCED IN SURVEY BY D.W.A., (DANIEL W. ALTENBURG) COUNTY SURVEYOR, DATED NOV. 1875 IN "MINUTES OF SURVEY" SECTION 17, ON FILE AT GRATIOT COUNTY ROAD COMMISSION. "POST 2" X 2".
 WITNESSED BY: OAK 30", N 51° W, .32 3/4 (21.615')
 BEECH 6", S 72 1/2° E, .14 1/2 ( 9.57')
 POST 3 E .50(33.00') "NW COR".
 SURVEY SHOWS DISTANCE NORTH OF 40.16 CH. (2650.56'), EAST OF 39.96 CH (2637.36'), SOUTH OF 40.39 CH. (2665.75') AND WEST OF 40.09(2645.94')
- 3. NO OTHER REFERENCES FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 12" WOOD ANCHOR POST ON FENCELINE EAST-WEST AND SOUTH. TRAVERSED ENTIRE SECTION 17 AND FOUND INTERSECTION OF 1/4 LINES TO FALL INSIDE OF ANCHOR POST. PROPORTIONAL LOCATION OF CORNER USING ALTENBURG'S DISTANCES OF 1875 WOULD PLACE CORNER ABOUT 5 FT. (1.52m) EAST OF INTERSECTION OF 1/4 LINES. REMOVED ANCHOR POST, SET STANDARD REMON. PIPE AT INTERSECTION OF 1/4 LINES AND RESET ANCHOR POST TO SOUTHEAST OF CORNER. MONUMENT SET ABOUT 1.0 FT. (0.3m) DEEP ALONG NORTHWEST SIDE OF ANCHOR POST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: D-6: TOWN 9 NORTH, RANGE 2 WEST, WASHINGTON TOWNSHIP, GRATIOT COUNTY. SET STANDARD GRATIOT COUNTY REMONUMENTATION PIPE WITH BRASS CAP AT INTERSECTION OF 1/4 LINES. WITNESSED BY:

- SET N & T #30090, SW/S TW.15" POPLAR, S 46° E, 14.02' ( 4.274m)
- SET N & T #30090, SE/S 27" OAK, N 53° E, 31.70' ( 9.664m)
- SET N & T #30090, SE/S 15" MAPLE, N 62° E, 55.79' (17.006m)
- SET N & T #30090, E/S 15" MAPLE, N 20° E, 40.26' (12.270m)

BEARINGS GIVEN ARE MAGNETIC. STANDARD MONUMENTATION CONSISTS OF A BERNTSEN STAINLESS STEEL 30"(762mm) X 2 3/8"(0.65mm) PIPE WITH A BRASS CAP STAMPED "GRATIOT COUNTY REMONUMENTATION", P.S. #30090.



LIBER 3 PAGE 179

Signed by David R. Lohr Date 7/19/99

Surveyor's Michigan License No. 30090

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 7/21/99

William Tingley, PS, Chairman