

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
GRATIOT COUNTY
RECORDED

22 JUL 99 11:56 A.M.

JANET M. DAVIS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION
For corners in
GRATIOT
(County)

Located In: Corner Code #

WASHINGTON TWP.

- | | | | |
|------------------------------------|------|------|-----|
| 1. Public Land Survey | T 9N | R 2W | F-1 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |
4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID R. LOHR, in a field survey on JUNE 3, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. CORNER NOT SET IN GLO SURVEY.

2. CORNER REFERENCED IN SURVEY BY R.J. FRAKER, COUNTY SURVEYOR, DATED DEC. 1877. WITNESSED BY:
LYNN 10" EAST 3 1/2" (2.31')
BLM 5" S 50° E 82L (54.12')

SURVEY SHOWS DISTANCE SOUTH OF 39.07CH (2578.62'), DISTANCE WEST OF 40.14CH (2649.24'), DISTANCE EAST OF 40.14CH (2649.24').

3. NO OTHER REFERENCES FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND #4 REBAR WITH SMASHED CAP 0.1' (30cm) BELOW GRAVEL SURFACE. TRAVERSED ENTIRE SECTION AND DETERMINED THAT FOUND IRON CLOSELY MATCHES F-13 NORTH STAR TOWNSHIP, BEING ABOUT 0.06 FT. (18cm) WEST OF MID-POINT BETWEEN E-1 AND G-1, HOWEVER IT LIES ABOUT 1.28 FT. (0.39m) SOUTH OF TRUE TOWNSHIP LINE. F-1 LIES 8.75FT. (2.667m) WEST OF F-13. COULD FIND NO EVIDENCE OF THE LOCATION OF F-1 AS A 36" (0.914m) CONCRETE STORM PIPE CROSSES GRANT ROAD AT THAT LOCATION. SET STANDARD REMON. PIPE CUT TO LENGTH OF 0.88FT. (0.268m) DUE TO SHALLOW CONCRETE STORM PIPE CROSSING. STANDARD PIPE SET IN 12" (305cm) STEEL AUTOMOTIVE WHEEL HOUSING AND SET WITH MANY ROCKS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-1: TOWN 9 NORTH, RANGE 2 WEST, WASHINGTON TOWNSHIP, GRATIOT COUNTY. SET MODIFIED REMON. PIPE, SET IN STEEL COLLAR AND WITH SMALL ROCKS, OVER TOP OF CONCRETE STORM PIPE. WITNESSED BY:

- ET #4 REBAR WITH CAP #30090, S 72° W, 43.00' (13.107m)
- ET #4 REBAR WITH CAP #30090, S 70° E, 43.00' (13.107m)
- ET #4 REBAR WITH CAP #30090, N 74° W, 43.00' (13.107m)
- 13, NORTHSTAR (STANDARD PIPE), N 85° E, 8.75' (2.667m)

BEARINGS GIVEN ARE MAGNETIC. STANDARD MONUMENTATION CONSISTS OF A BERNTSEN STAINLESS STEEL 30" (762mm) X 2 3/8" (0.65mm) PIPE WITH A BRASS CAP STAMPED "GRATIOT COUNTY REMONUMENTATION", P.S. #30090.



signed by David R. Lohr

Date 7/19/99

Surveyor's Michigan License No. 30090

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT A MEETING HELD 7/21/99

WGT
William Tindley, DC