

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

GRATIOT (County)

Located In:

Corner Code #

STATE OF MICHIGAN GRATIOT COUNTY RECORDED

22 JUL 99 11:58 A.M.

JANET M. DAVIS REGISTER OF DEEDS

Register of Deeds Stamp & File Number

WASHINGTON TWP.

Table with columns for survey types (Public Land Survey, Property Controlling, etc.) and grid coordinates (T 9N, R 2W, G-8).

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

I, DAVID R. LOHR, in a field survey on FEBRUARY 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. CORNER SET BY AUSTIN BURT, DEPUTY SURVEYOR, IN MAY 1852. "S 15° E, CORRECTED BETWEEN SECS. 21 + 22," AT A DISTANCE OF 40.16 "OLD QR. COR.". WITNESSED BY: LYNN 10" N 14° E, 26 L (17.16') LYNN 14" S 38° W, 25 L (16.50') GLO NOTES SHOW DISTANCE NORTH OF 40.16 CH. (2650.56') AND SOUTH OF 40.17 CH. (2651.22') 2. CORNER REFERENCED IN "MINUTES OF SURVEY" ON FILE AT GRATIOT COUNTY DRAIN OFFICE, PAGE 21, DATED NOV. 1875, BY D.W.A. (DANIEL W. ALTENBURG), "SEE SEC. 22" "POST 2 X 2 - OCF". WITNESSED BY: S. ELM, 10", S 84 1/2° E, 58 1/2 L (38.61') BEECH 8", N 71 3/4° W, .61 L (40.26') SURVEY SHOWS DISTANCE NORTH OF 40.17 CH. (2651.22') AND WEST OF 40.1425 CH (2649.05') 3. CORNER REFERENCED IN COUNTY SURVEYOR NOTES ON PAGE 146, DATED NOV. 1875, BY D.W.A. (DANIEL W. ALTENBURG), SAME NOTE AND WITNESSES AS ITEM #2 ABOVE. SURVEY SHOWS SAME DISTANCES AS ITEM #2 ABOVE. 4. ORNER REFERENCED IN LCRC RECORDED IN LIBER 1, PAGE 477, BY JERRY L. WILCOX, RLS #14102, DATED 10/16/79, "FD. BOAT SPIKE 2' NORTH OF CENTERLINE E-W, 7' WEST CENTERLINE N-S" WITNESSED BY: N 14° W, 51.18', 30" RED OAK (GONE) N 29° W, 19.22', STEEL FE. POST (GONE) S 29° W, 31.91', CENTER TOP UTILITY BOX (FD) S 18° W, 31.08', N. EDGE ROAD SIGN POST (GONE) 5. CORNER REFERENCED BY JOHN McLANE, PS #28415, IN MICH. CON. GAS CO. SURVEY, DATED 4/07/82, ON PAGE 6B, GRATIOT COUNTY FIELD BOOK #2. "SET 5/8" IRON ROD FROM TWO REMAINING WITNESSES ON P.A. 74 BY JERRY L. WILCOX, R.L.S.#14102 IN LIBER 1, PAGE 477 ON DEC. 28, 1979. CORNER IS 2' NORTH OF C/L RANGER ROAD (20' GRAVEL) & 7' WEST OF C/L BALDWIN ROAD (20' GRAVEL)." WITNESSED BY: FD. NAIL E/S 30" RED OAK - AZ. 349°, 51.18' SET NAIL W/RLS TAG IN S/S OF WEST TWIN 8" MAPLE - AZ. 93°, 68.91' SET NAIL W/RLS TAG IN S/S MULTI. 36" COTTONWOOD - AZ. 288°, 20.65' TOP CENTER OF BURIED TELEPHONE JUNCTION BOX - AZ. 211°, 31.91' "NO OTHER AVAILABLE"

COMPUTATION SHEET SHOWS DISTANCE NORTH OF 2652.70', SOUTH OF 2651.96' AND WEST OF 2647.89.

6. NO OTHER REFERENCES FOUND

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND #5 X 18" ((450mm) STEEL PIN, 1.0' ((305mm) BELOW GRAVEL SURFACE, ON C/L RANGER ROAD AND 6 FT. (1.828m) WEST C/L BALDWIN ROAD. EXCAVATED 5 FT. (1.524m) X 5 FT. (1.524m) X 2.3 FT. (0.701m) DEEP THRU GRAVEL INTO HEAVY CLAY. FOUND NOTHING. 8" (200mm) PVC TILE HAS BEEN RUN THRU CORNER LOCATION FROM SE TO NW DESTROYING ANY OLD EVIDENCE. EXPANDED EXCAVATION EAST TO INCLUDE C/L-C/L OF ROADS. FOUND WHAT APPEARED TO BE BARREL OF ROCKS AND BROKEN TILE BUT WHICH ENDED UP BEING FILL INTO A PROBABLE BLOW HOLE IN THE REMAINS OF OLD 18" CLAY TILE ALSO RUNNING THRU INTERSECTION FROM SE TO NW. OLD TILE INVERT WAS 3.5 FT. (1.06m) DEEP. FINAL EXCAVATION SIZE BEING 12 FT (3.658m) X 4 FT (1.22m) X 3 FT (0.914m) DEEP. ACCEPTED LOCATION OF #5 STEEL PIN AS CORNER AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER AND SET STANDARD GRATIOT REMONUMENTATION PIPE WITH BRASS CAP AT ITS LOCATION.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8: TOWN 9 NORTH, RANGE 2 WEST, WASHINGTON TOWNSHIP, GRATIOT COUNTY. SET STANDARD GRATIOT REMONUMENTATION PIPE WITH BRASS CAP AT LOCATION OF FOUND #5 STEEL PIN. WITNESSED BY:

- TRAV. PT. #1252(#4 REBAR), S 06° W, 280.03' (85.354m) TOP C/L OF TELEPHONE FED., S 32° W, 31.30' (9.540m) STOP SIGN, N 17° W, 25.41' (7.745m) SET #4 REBAR/CAP #30090, N 23° E, 53.36' (16.264m) SET PK NAIL IN TOP 18" (450mm) CMP, N 18° W, 28.42' (8.663m) SET #4 REBAR/CAP #30090, S 70° E, 45.44' (13.850m) STOP SIGN, S 35° E, 31.77' (9.684m) BEARINGS GIVEN ARE MAGNETIC. STANDARD MONUMENTATION CONSISTS OF A BERNTSEN STAINLESS STEEL 30" (762mm) X 2 3/8" (0.65mm) PIPE WITH A BRASS CAP STAMPED "GRATIOT COUNTY REMONUMENTATION", P.C. #30090.

Signed by David R. Lohr Date 7/19/99

Surveyor's Michigan License No. 30090 ACCEPTED BY THE GRATIOT COUNTY SURVEY BOARD GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 7/22/99



LIBER 610 PAGE 190