

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	, T. <u>9</u> N. S., R. <u>2</u> E. W.	<u>3, 4, 8</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Russell L. Roon, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- | | | |
|--|--|---|
| <p>3 - Set halfway and on line between C-9 and C-10.</p> | <p>4 - Set at intersection of 1/8 lines.</p> | <p>8 - Set halfway and on line between C-10 and D-10.</p> |
|--|--|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|--|---|
| <p>3 - Set 15' of 1" pipe in concrete with aluminum cap in pond. No witnesses available.</p> | <p>4 - Set concrete monument with aluminum cap #13593. No witnesses available.</p> | <p>8 - Set concrete monument with aluminum cap #13593.
 N 11° E 33.31' 6" Maple
 N 58° E 26.81' 25" Twin Maple
 S 01° E 32.40' 19" Maple
 N 72° W 54.45' 13" W. Ash</p> |
|--|--|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Russell L. Roon CHIEF OF SURVEY PARTY DATE 1-8-80
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13593