

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>30</u> T. <u>9</u> N. S., R. <u>2</u> W.		A-11, B-11
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

9

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Russell L. Roon, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>A-11 Found no evidence of old corner. Set concrete monument on line and 89.76' north of SE Cor., Sec. 25, T9N, R3W, as called for in G.L.O. notes.</p>	<p>B-11 Found remains of old post under large stone.</p>
--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>A-11 Set concrete monument with aluminum cap stamped RLS 13593, 12/77.</p> <p>N 72° E 18.0' Fence north and east S 44° E 70.23' NW Cor. House S 17° E 59.28' 20" Maple S 77° W 77.62' Power Pole</p>	<p>B-11 1" Iron pipe with plastic cap.</p> <p>N 70° E 42.84' 17" Cottonwood S 84° E 37.05' 6" Ash S 36° E 66.27' 10" Twin Ash West 20' C State Road</p>
---	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Russell L. Roon CHIEF OF SURVEY PARTY DATE 1-8-80
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13593