

FEB 10 2000

**GRATIOT COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 605 PAGE 840
GRATIOT CO. MICH.
RECORDED

SECTION

For corners in Gratiot (County) Located In: _____ Corner Code # _____
Township _____

1. Public Land Survey T 09N R 02W A01
T 09N R 03W M01
T 10N R 02W A13
T 10N R 03W M13

2. Property Controlling S T R
In Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

'99 APR 27 AM 8 34

Janet M. Davis
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William G. Tingley, in a field survey on _____ 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found, as expressed below.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831, Joel Wright, G.L.O. Notes
Intersect N. boundary at end of 5 miles
(no witnesses given)

Sept. 1872 D.W.A., Field Book
Stone marked T.C.
Stone S52 W. 71 1/4
Stone N45 W. 60 o.c.f.

Oct. 1876, D.W.A., Record of Minutes of Survey, Liber B, Page 228
(Stone on Top) Stone cor. T.C. 8"x10"x24"
Stone S 52° W 71 1/4
Stone N 45° W 60

May 1892, D.W.A., Record of Minutes of Survey, Liber C, Page 203
Stone Cor. 8"x10"x24" T.C.
Stone S. 52°W. 71 1/4
Stone N. 45°W. 60

August 12, 1996, Mark L. VanRaemdonck, Recorded Survey, Liber 561, Page 1429
Pipe in Monument Box

S30°W 66.43' N&T #24622 N. face util. pole
N60°E 41.58' N & T #19003 Se face util. pole
N35°W 33.05' N. end 18" CMP
East 3.30' Centerline road
N&T N. Sd PP 110° Az. 121.55'

1852, Austin Burt, G.L.O. Notes
Intersect W. boundary at end of 5 miles
Beech 12 N8 W13
Beech 8 S45 E25

Oct. 1876, D.W.A., Field Book
Stone 8x10x24 nr T.C.
Stone S52 W 71 1/4
Stone N45 W. 60
Post 12 N 40 E. 37 3/4
Post 10 S 34 3/4 E. 57 1/2

D.W.A., Record of Minutes of Survey, Liber A, Page 272, Liber B, Page 119
Stone Cor 8"x10"x24"
Stone S52° W. 71
Post 12 N 40° E 37 3/4
Post 10 S 34 3/4 E. 57

1892, D.W.A., Record of Minutes of Survey, Liber B, Page 107
Stone cor T.C.
Stone South 52°W 71 1/4
Stone N 45° W. 60

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1"x1' iron pipe in monbox over stone and bits of clay tile.
Found Nail & Tag #19003 south side power pole N60°E 41.70 Feet
Found Nail & Tag #30104 north side power pole S70°E 120.59 Feet
Found Nail & Tag #24622 north side power pole S35°W 66.38 Feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Remonumentation corner between stones and over bits of clay tile.
Found Nail & Tag #19003 south side power pole N60°E 41.70 Feet
Found Nail & Tag #30104 north side power pole S70°E 120.59 Feet
Found Nail & Tag #24622 north side power pole S35°W 66.38 Feet
Center of catch basin N40°W 40.33 Feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 3/18/98

Surveyor's Michigan License No. 30104

ACCEPTED BY THE GRATIOT COUNTY SURVEY FEES GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 3/18/98

WGT
William Tingley, PS, Chairman

