

GRATIOT COUNTY REMONUMENTATION PROGRAM

GRATIOT CO. MICH. RECORDED

MAR 23 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'98 DEC 22 AM 10 53

SECTION

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
Gratiot	Township	
1. Public Land Survey	T 9N R 3W	M-2
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William G. Tingley, in a field survey on 02/26/98 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1831, Joel Wright, G.L.O. Notes**  
Set qr. sec. post  
Beech 13 N28 W48  
R. Oak 36 S44 1/2 W37
- Sept. 1872, D.W.A., Field Book**  
post 4x4  
O.B. R Oak 36 S44 11/2 W 37 o.c.f.
- 1892, D.W.A., Record of Minutes of Survey, Liber B, Page 107**  
Oak post 4"x4" & stones  
Butternut at S.E. 1.16 - Tel. pole N.W. 61- fence E. 42 lks.
- Oct. 1, 1987, William B. Ruddell, Recorded Survey, Liber 476, Page 130**  
Fnd pipe under BT  
W. 38.55 N&C in FP  
3' E of CL RD



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 1"x1" pipe with remains of red cap over 3"x1/4" rod over stones and rotted remains of wood post.**  
 Found nail and tag south fence post N83°W 38.70 Feet  
 South end 18" corrugated metal pipe S45°W 51.00 Feet  
 South end 12" corrugated metal pipe N20°E 68.50 Feet  
 10" stone East side ditch S25°E 138.90 Feet

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 3/16/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: WGT  
William Tingley, PS, Chairman

- Set standard Remonumentation corner between stones and in wood post.**  
 Found nail and tag south fence post N83°W 38.70 Feet  
 South end 18" corrugated metal pipe S45°W 51.00 Feet  
 South end 12" corrugated metal pipe N20°E 68.50 Feet  
 10" stone East side ditch S25°E 138.90 Feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 3/16/98  
 Surveyor's Michigan License No. 30104

LIBER 598 PAGE 106

379