

SEP 08 1999

**GRATIOT COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

GRATIOT CO. MICH.
RECORDED

'95 DEC 20 PM 1 29

SECTION

For corners in
Gratiot
(County)

Located In: North Shade Township

Corner Code # _____

1. Public Land Survey Sec 6 T 9 N R 4 W A-1, NW Corner
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Janet M. Davis
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field survey on June 30, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes

West on South Boundary, Section 31, T10N-R5W
75.50 chains - intersect West boundary of the end of 5 miles 79 chains, 16 links
Sugar 16" S42-1/2°E 25 links
Sugar 14" N21-1/2°E 21 links
North on East Boundary Section 1, T9N-R5W, 79.16 chains - intersect North Boundary at end of 5 miles 75 chains, 50 links

1869, D.W. Altenburg, Gratiot County Surveyor, Liber B, Page 16, Record of Minutes of Survey

Post 3" x 3"
Pine Stump 40" N32-1/2°E 50 links
Beech 16" S40-1/2°E 61 links
1891, Edward Jones, County Surveyor
Pine Stump 42" N25-1/4°E 76 links
Pine Stump 42" S66°E 102 links

1935, R.D. McNutt, County Surveyor, Record Cards

und stone
ouble Wild Cherry Southeast 47.0 feet
1968, Salisbury and Saunders, Surveyors in Consumers Power Company Survey
Found stone
28" White oak S55°E 28.4 feet
Telephone Pole S45°W 40.8 feet
Telephone Pole N45°W 90.7 feet

1975, Montcalm County Road Commission

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found rered at surface
Found 3/4" pipe below rered
Found stone on Eastside of rered (point end up 0.8' x 0.8' x 1.3')
Found crockery around stone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation corner in place of stone (left stone beside)
Found nail in Power Pole S35°W 89.25 feet
Found nail in 23" Hickory S30°E 90.37 feet
Centerline of 3" Oak N55°E 90.40 feet
Top, Center of Cable Riser Box West 24.95 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 12-22-1995

Surveyor's Michigan License No. 30104

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE GRATIOT COUNTY SURVEYOR GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95

WGT
William Tingley, PS, Chairman

