

SURVEY & REMONUMENTATION

FEB 10 2000

LIBER 619 PAGE 929

GRATIOT COUNTY REMONUMENTATION PROGRAM

SECTION

LAND CORNER RECORDATION CERTIFICATE

STATE OF MICHIGAN
GRATIOT COUNTY
RECORDED

Filing Requirement of Act 74, Mich. P.A. 1970

11 JAN 2000 9:35 A.M.

JANET M. DAVIS
REGISTER OF DEEDS

For corners in
Gratiot
(County)

Located In: North Shade Township

Corner Code #

1. Public Land Survey	Sec. 31	T <u>09</u> N R <u>04</u> W	<u>A-13</u> ✓
		T <u>09</u> N R <u>05</u> W	M-13
		T <u>08</u> N R <u>04</u> W	A-01
		T <u>08</u> N R <u>05</u> W	M-13
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, William G. Tingley, in a field survey on November 4, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 March 7, 1831 Robert Clark Jr. DS. Intersected west boundary at end of 5. 75. 86.
 Witnesses: Sugar 14" S11°W, 14 links; Beech 10" N21°E, 38 links. December 14-17, 1869. D.W. Attenburg, DS. Post corner 2 X 2 - stones - and stones on corner. No witnesses given
 April 10, 1902 Charles Eddy, County Surveyor, Commencing at the NW corner of said section found stone for corner witnessed by: Apple 1 1/2" S11°E 69 links.
 LCRC by Thomas Mueller, PS, # 25861, dated February 17, 1981, Liber 002 page 16, T09N-R04W, North Shade Township, Gratiot County. Found Shaft of P.K. nail in blacktop at centerline of intersection, witnessed by:
 SW power pole 40.58 feet
 NW Telephone pole 47.90 feet
 NE road sign post 37.80 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found PK nail as filed in LCRC, Liber 2, page 16, Gratiot County Records by Thomas Mueller, PS. Dug through 6" of asphalt and found stake and pointed stone set in cairn of stones. Accepted pointed stone in cairn of stones as a careful and faithful reestablishment of the position of the original corner.

Placed 1/2" rod to point of stone and set Clinton County Monument and Monument box* Liber 4-Page 175

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SW Corner, Section 6
 *Set Standard Clinton County Monument and monument box.
 Nail and tag #13039 in NE side Power Pole S73°E 139.91 feet
 Nail and tag #13039 in SW side Telephone pole N40°W 47.70 feet
 Nail and tag #13039 in NW side Power pole S69°W 67.00 feet
 Nail and tag #13039 in NW side Power pole S47°W 40.70 feet

ACCEPTED BY THE GRATIOT COUNTY SURVEY GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 12/30/99
WGT
 William Tingley, PS, Chairman

* Standard Clinton County Monument is a 2 1/2 " dia. Steel tube 30" long with a stamped brass cap and breakaway magnetic base.

Signed by: William Tingley Date: 12/30/99
 Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993



	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

LIBER 619 PAGE 201