

SURVEY & REMONUMENTATION

SEP 08 1999

GRATIOT COUNTY REMONUMENTATION PROGRAM

LIBER 562 PAGE 1308

GRATIOT CO. MICH. RECORDED

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'96 NOV 26 PM 2 33

For corners in Gratiot Located In: Hamilton Corner Code # _____
 (County)

1. Public Land Survey Sec T 10N R 1W C-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Janet M. Davis
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on September 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1831, R. Thomas, Deputy Surveyor, GLO Notes
 80.00 chains Set Post Corner Sections 29,30, 31, 32
 Black Ash 8" S64°W 15 links
 Black Ash 12" N16°E 52 links
 - 1879, Thomas Harrod, Deputy County Surveyor, Liber B, Page 289, Record of Minutes of Survey
 White Ash Post 4" x 4" - Old Corner Found
 Swamp Elm 5" S35-1/2°W 25 links
 Black Ash 8" S60°W 26 links
 - County Records (no date)
 Black Ash post and stones
 Northeast Corner Brick School House S48°20'W 1.97-1/2 chains (130.35 feet)
 - 1955, Consumers Power Company - Survey of feelands for transmission line Right-of-Way
 Found Stone, set "T" iron
 Bridge Post Northwest 25.00 feet
 Bridge Post Northeast 25.00 feet
 - 1977 D. Hunter #19177, LCRC, Liber 1, page 409 (apparently C-11 and C-12 were transposed on this LCRC.
 the following were given for C-12): Found "T" bar
 Road Sign Southwest 42.0 feet
 Northwest Corner of Wing Wall Northwest 26.42 feet
 Telephone Cable Marker Northeast 35.80 feet
 - 1978 R.J. Crater #16924, LCRC, Liber 1, Page 441
 Found "T" iron
 Road Sign Southwest 42 feet
 Northwest Corner of Wing Wall Northwest 26.46 feet
 Telephone Cable Marker Northeast 35.80 feet



- Also set following bearing objects:
- North end 24" CMP (culvert) Northwest 49.10 feet
 - Northwesterly Post on Southeast Wing Wall Railing N35°E 26.11 feet
 - P.K. (masonry) Nail in Westend South Abutment Wall of Bridge N15°W 26.25 feet
 - Power Pole N35°W 66.05 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found "T" iron.
 Found nail in Southside Power Pole N45°W 65.93 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Remonumentation Monument over "T" iron.
 Nail in Southside Power Pole N45°W 65.93 feet
 Set Nail and Tag Eastside Telephone Pole N45°E 56.89 feet
 Set Nail and Tag Northside Telephone Pole S45°E 43.42 feet
 Centerline south end 24" CMPipe S55°W 46.50 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley
 Surveyor's Michigan License No. 30104

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971 PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/3/96
 REVISED MAY 18, 1976
 REVISED JAN., 1963
 ADAPTED FOR WORD PROCESSING MARCH, 1993