

**GRATIOT COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Gratiot
(County)

Located In: Hamilton Township

Corner Code #

1. Public Land Survey	Sec 4	T <u>10</u> N R <u>1W</u>	<u>E-1, N 1/4</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

27 OCT 1999 12:59:30 PM

LORI A. WILSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1							○						
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William G. Tingley a field survey on December 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Not set GLO

1906, E.W. Redman, County Surveyor, Field Book 10-1, Pages 20 and 21
1" Pipe 2 foot long and stones
Maple 16" S82°W 255 links
Apple 3" S42-1/4°E 89-7/8 links
Plowpoint North 33-1/5 links
Liber D, Page 109, Record of Minutes of Survey
Same Data

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-19-99

WGT
William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
+/- 2 feet below surface found a 1" pipe in stones 5 feet North of Centerline of pavement on field line to the South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Remonumentation Monument over 1" pipe

Set Nail & Tag Westside Power Pole	N12°E	147.55 feet
Set Nail & Tag Northside Power Pole	S63°W	170.72 feet
Northeast Corner Barn	S39°W	180.56 feet
Set Nail & Tag Northside Guy Pole	S81°E	429.91 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 11-19-99, 1997
Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

REC
MAY 03 2000

SECTION

