

GRATIOT COUNTY REMONUMENTATION PROGRAM

FEB 22 1996

LAND CORNER RECORDATION CERTIFICATE

GRATIOT CO. MICH. RECORDED

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

'95 DEC 20 PM 1 28

For corners in
Gratiot
 (County)

Located In: North Star Township

Corner Code # _____

1. Public Land Survey Sec 6 T 10 N R 2 W A-2, W 1/4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, William Tingley a field survey on November 1, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1874, D.W. Altenburg, County Surveyor, Liber B, Page 48 and Field Book 10-2, Pages 100 and 101
 Post 3" x 3" and Iron Bar by side
 Maple 2" N77°E 32-1/2 links
 Post 4" S81-1/2°E 50-3/4 links
 Stone 1/4 Post Section 1, T10N-R3W South 8-1/2 links (5.61 feet)
 1974, D.B. Whittier #10070, LCRC, Liber 1, Page 181 for M-2 (E 1/4 Section 1, 10-3)
 Monument Box for corner East North 5.47 feet

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1" Iron pipe in Monument box in bituminous pavement. 1 foot deep found another monument box in concrete pavement. At 0.8 feet below top of second box found stones (2), one under pipe and 1 beside.
 Found pipe over pointed stone South 5.38 feet -- E 1/4, Section 1, 10-3
 Found Nail and Tag in Power Pole N40°W 38.45 feet
 Found Nail and Tag #17640 in Power Pole S40°E 39.95 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner over stone in Monument Box
 Found Nail and Tag in Power Pole N40°W 38.45 feet
 Found Nail and Tag #17640 in Power Pole S40°E 39.95 feet
 Set Nail and Tag in Power Pole S28°W 106.60 feet
 Found Light Gauge Railroad Rail (center) S85°E 28.35 feet
 Standard Corner South 5.38 feet

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11/29/95.

WGT
William Tingley, PS, Chairman

This corner is accepted as the best available evidence of the position of the original corner.

Signed by William Tingley Date 12-12, 1995

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
 REVISED MAY 14, 1978
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993

