

FEB 22 1996

GRATIOT COUNTY REMONUMENTATION PROGRAM

GRATIOT CO. MICH.

LAND CORNER RECORDATION CERTIFICATE

RECORDED

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

'95 DEC 20 PM 1 28

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Form with fields: For corners in Gratiot (County), Located In: North Star Township, Corner Code # A-3, W. Bndry, 1. Public Land Survey Sec 6 T 10 N R 2 W, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

Grid table with columns A-M and rows 1-13. Row 3, column A contains a black dot.

I, William Tingley a field survey on July 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: GLO Notes

1852, Resurvey of 10-2 Austin Burt, Deputy Surveyor S89°50'W Random between Section 6 and 7 71.74 chains intersect West boundary 8 links South of Corner N89°43'E corrected between 6 and 7 Old Bearing Sugar 12" S67°E 41 links Old Bearing Sugar 14" N37°E 37 links

1871, D.W. Altenburg, County Surveyor, Liber B, Page 47, Record of Minutes of Survey Post 3" x 3", old section corner found Elm 6" S46-3/4°E 86 links White Oak 3" N47-1/2°E 105 links

1967, Merrill Hunter, Job No. E-107 and E-107A Found corner 9.24 feet North of Southeast Corner, Section 1, T10N-R3W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 1" Iron Pipe 1.65 feet long in Monument Box 9.68 feet North of Southeast corner Section 1, 10-3 Below Iron pipe found a large (10 pound) pointed stone. Below stone 2.4 feet deep found a 3/4" Iron Pipe driven into wood stake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner in Monument Box over 1" Iron Pipe Set Nail and Tag in 6" Elm N52°E 76.2 feet Found Nail and Tag in Power Pole S45°E 65.11 feet Found Nail and Tag in Power Pole S30°W 94.40 feet Found Nail and Tag in Power Pole N40°W 51.67 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 12-12-1995

Surveyor's Michigan License No. 30104

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11 29 95.

WGT. William Tingley, PS, Chairman

