

APR 20 1999

GRATIOT COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

LIBER 605 PAGE 838

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH. RECORDED

'99 APR 27 AM 8 34

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Gratiot (County)

Located In:

Corner Code #

Township

1. Public Land Survey

T 09N R 02W
T 09N R 03W
T 10N R 02W
T 10N R 03W

A01
M01
A13
M13

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. Recorded Plat

5. Private Claims

Grid table with columns A-M and rows 1-13. Values range from 6 to 36.

I, William G. Tingley, in a field survey on 19, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831, Joel Wright, G.L.O. Notes
Intersect N. boundary at end of 5 miles
(no witnesses given)

1852, Austin Burt, G.L.O. Notes
Intersect W. boundary at end of 5 miles
Beech 12 N8 W13
Beech 8 S45 E25

Sept. 1872 D.W.A., Field Book
Stone marked T.C.
Stone S52 W. 71 1/4
Stone N45 W. 60 o.c.f.

Oct. 1876, D.W.A., Field Book
Stone 8x10x24 mr T.C.
Stone S52 W 71 1/4
Stone N45 W. 60
Post 12 N 40 E. 37 3/4
Post 10 S 34 3/4 E. 57 1/2

Oct. 1876, D.W.A., Record of Minutes of Survey, Liber B, Page 228
(Stone on Top) Stone cor. T.C. 8"x10"x24"
Stone S 52° W 71 1/4
Stone N 45°W 60

D.W.A., Record of Minutes of Survey, Liber A, Page 272, Liber B, Page 119
Stone Cor 8"x10"x24"
Stone S52° W. 71
Post 12 N 40° E 37 3/4
Post 10 S 34 3/4 E. 57

May 1892, D.W.A., Record of Minutes of Survey, Liber C, Page 203
Stone Cor. 8"x10"x24" T.C.
Stone S. 52°W. 71 1/4
Stone N. 45°W. 60

1892, D.W.A., Record of Minutes of Survey, Liber B, Page 107
Stone cor T.C.
Stone South 52°W 71 1/4
Stone N 45° W. 60

August 12, 1996, Mark L. VanRaemdonck, Recorded Survey, Liber 561, Page 1429
Pipe in Monument Box
S30°W 66.43' N&T #24622 N. face util. pole
N60°E 41.58' N & T #19003 Se face util. pole
N35°W 33.05' N. end 18" CMP
East 3.30' Centerline road
N&T N. Sd PP 110° Az. 121.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1"x1' iron pipe in monbox over stone and bits of clay tile.
Found Nail & Tag #19003 south side power pole N60°E 41.70 Feet
Found Nail & Tag #30104 north side power pole S70°E 120.59 Feet
Found Nail & Tag #24622 north side power pole S35°W 66.38 Feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Remonumentation corner between stones and over bits of clay tile.
Found Nail & Tag #19003 south side power pole N60°E 41.70 Feet
Found Nail & Tag #30104 north side power pole S70°E 120.59 Feet
Found Nail & Tag #24622 north side power pole S35°W 66.38 Feet
Center of catch basin N40°W 40.33 Feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley
Surveyor's Michigan License No. 30104

Date 3/18/98



LIBER 605 PAGE 112

ACCEPTED BY THE GRATIOT COUNTY SURVEYOR GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 3/18/98

WOT
William Tingley, PS, Chairman