

**SURVEY & REMONUMENTATION**

LIBER **541** PAGE **268**

**GRATIOT COUNTY REMONUMENTATION PROGRAM**

**APR 27 1995** Corner approved by Peer Group on \_\_\_\_\_, 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Gratiot Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey Sec 6 T 10 R 2 B-3, S 1/4  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

GRATIOT CO. MICH.  
 RECORDED  
 '94 DEC 1 PM 4 00  
*Janet M. Davis*  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on July 27, 1994  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 July 21, 1852, Austin Burt, Deputy Surveyor, GLO Notes

- Set Post
- Beech 6" S40°E 25 links
- Beech 12" N36°W 37 links

December 1874, D.W. Attenburg, County Surveyor, Liber B, Page 47

- Post Corner, 2" x 2"
- Sugar 18" S33°E 60-1/2 links
- Sugar 16" S45-1/2°W 35 links

December 1874, D.W. Attenburg, County Surveyor, Liber A, Page 396

- Oak Post 3 x 3
- Sugar 18" S33°E 60-1/2 links
- Sugar 16" S45-1/2°W 35 links

No name or date given, Gratiot County Road Commission Record of Minutes of Survey

1-3/4" Pipe with part of elbow at Northside of stone

- Center 12" Maple Northeast 60.5 feet
- Center 8" Power Pole Northwest 29.7 feet

January 1987, George M. Young, #17640, Survey Liber 471, Page 1037

- 1-1/4" Pipe
- Nail & Tag 8" Pine Northeast 20.7 feet
- Nail & Tag Power Pole Southeast 84.95 feet
- Nail & Tag Power Pole Northwest 23.95 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone corner with 1-3/4" Iron Pipe on Northside

- Found Nail and Tag Power Pole S60°E 84.73 feet
- Found 12" Maple Northeast 60.5 feet (now 28", 60.8')
- Found 8" Pine N10°E 21.3 feet (now stump)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner over stone next to 1-3/4" pipe

- Nail and Tag Maple NW
- Nail and Tag Power Pole N05°W 24.47 feet
- Found Nail and Tag Power Pole S60°E 84.73 feet
- 8" Pine Stump N10°E 21.3 feet
- Set Nail & Tag Northside Power Pole S80°W 157.75 feet

This corner is accepted as a careful and faithful reestablishment of the position of the original corner and is accepted as the best available evidence of the position of the of the original corner.

Signed by William Tingley Date Aug 1994  
 Surveyor's Michigan License No. 30104



ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD Aug 29

*William Tingley*  
 William Tingley, PS, Chairman

15  
 9/17  
 R. File