

GRATIOT COUNTY REMONUMENTATION PROGRAM  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH.  
 RECORDED

'96 DEC 26 AM 10 3

*Janet M. Davis*  
 REGISTER OF DEEDS

For corners in Gratiot Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey Sec 1 T 10 N R 2 W ✓ M-1. NE Corner  
 Sec 6 T 10 N R 1 W A-1. NW Corner  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on December 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes  
 79.55 chains, intersected North boundary 17.73 chains East of Towns 11, Ranges 1 and 2 West  
 Sugar 14" S79°E 33 links  
 Swamp Oak 30" S65°W 38 links

1878, D.W. Altenberg, County Surveyor, Liber A, Page 266 and Liber B, Page 96, Record of Minutes of Survey at Gratiot County Drain Commission Office  
 2" x 2" post  
 Oak 40" S65°W 38 links  
 Oak 14" S66°E 57-1/2 links

1905, E.W. Redman, County Surveyor, Pages 90-91, Field Book 10-2  
 Old Corner found, same bearing trees as 1878. Also old corner found, Iron Rod and stone set  
 White Ash 4" N34°E 56-1/4 links

1900, J.W. Harrod, County Surveyor, Field Book 10-1, Page 24 and 25  
 Oak Stake  
 White Ash 4" N34°E 66-1/4 links

Also 1968 - no survey or name  
 Found Old Corners - set Monument Box  
 Box Elder Northwest 49 links

No date, County Road Commission Records  
 Monument Box  
 Nail in Telephone Pole West Southwest 198.45 feet  
 Nail in Telephone Pole East Southeast 209.38 feet  
 1394.05 feet West of North 1/4 Corner, Section 6.

Continued on Back .....

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 3/4" pipe in Monument Box 7.85 Feet North of Centerline of pavement of Washington Road. At 2 feet below pavement, found painted stone with 1" pipe on Northside.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over 3/4" pipe and pointed stone.  
 Found Spike Northside Telephone Pole S45°W 48.79 feet  
 Northwest Corner Telephone Box S45°E 48.67 feet  
 Westerly Leg Arrow Sign N25°E 24.67 feet  
 Center of 12" Birch N45°W 83.70 feet  
 7.85 feet North of Centerline East-West pavement on Centerline of Pavement South

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-17, 1995

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
 REVISED MAY 14, 1978  
 REVISED JAN. 1983  
 ADAPTED FOR WORD PROCESSING MARCH, 1993

SURVEY &  
 REMONUMENTATION

DEC 20 1995

LIBER

3 PAGE 95

1/7 File

Continued from front (M-1, 10-2 and A-1, 10-1)

LIBER 563 PAGE 1115

1973, John Radcliffe, LCRC, Liber 1, Page 47

Found 3/4" Pipe in Monument Box

Telephone Pole	S45°W	49.14 feet
Telephone Pole	S45°E	50.23 feet
Centerline Road	South	7.85 feet

In Survey, Liber 1, Page 27

Same Data as Liber 1, Page 47

1979, Gratiot County Road Commission  
Found 3/4" pipe in Monument Box

SURVEY &  
REMONUMENTATION

DEC 20 1999

SECTION

LIBER

3 PAGE 96