

**SURVEY &
REMONUMENTATION**

GRATIOT COUNTY REMONUMENTATION PROGRAM

LIBER **538** PAGE **511**
1994

AUG 31 1994

Corner approved by Peer Group on 5 Aug, 1994

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

**GRATIOT CO. MICH.
RECORDED**

'94 AUG 19 AM 10 09

Janet M. Davis
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | | |
|--|------------------------------|-------------------|
| For corners in <u>Gratiot</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | Sec 1 T <u>10</u> R <u>3</u> | <u>M-2, E 1/4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

I, William Tingley a field survey on August 1, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

May 1831, R. Clark, Jr., Deputy Surveyor, Page 294

Set post

Elm 14" S12°W 23 links
Sp. Oak 30" N66°W 11 links

May, 1871, D.W. Attenburg, County Surveyor, Liber B, Page 57

Stone 8" x 8"

Stone S55°W 54 links
Stone N57-1/2°W 48-1/2 links

Old 1/4 Corner Found 8-1/2 links South of W 1/4 6-10-2

Field Book, Gratiot County 10-3

Stone 8 x 8

Stone S55°W 54 links
Stone N57-1/2°W 48-1/2 links

Gratiot County Records, 1-10-3, Record of Minutes of Survey in Gratiot County Road Commission

Iron in Mon Box at East End of Webster Street, 0.8-1/2 links South of W 1/4 Corner 6-10-2

July 1974, David B. Whittier, #10070, LRCR, Liber 1, Page 181

Found Rod in Mon Box

North Mon Box to East 5.47 feet

Nail & Tag Northeast side Telephone Pole Northwest 42.65 feet

West to Centerline Manhole 12.65 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron Pipe in Mon Box

Below Iron Pipe found 8" x 8" Pointed Stone

Top of Stone is 2.3 feet deep

Accepted stone as Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner and Mon Box over Point of Stone

Found Nail and Tag in Power Pole N35°W 42.35 feet

Found Nail and Tag #17640 in Power Pole S45°E 36.40 feet

Set Nail and Tag in Power S30°W 101.55 feet

Light Gauge Railroad Rail N85°E 28.42 feet

W 1/4 Corner (1" Iron Pipe in Mon Box) 6-10-2 North 5.47 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 5 Aug, 1994

Surveyor's Michigan License No. 30104

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

