

**SURVEY & REMONUMENTATION**

LIBER **551** PAGE **1004**

SEP 08 1999

**GRATIOT COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH.  
RECORDED

'95 DEC 20 PM 1 29

*Janet M. Davis*  
REGISTER OF DEEDS

**SECTION**

For corners in \_\_\_\_\_  
Gratiot  
(County)

Located In: \_\_\_\_\_  
Newark Township

Corner Code # \_\_\_\_\_

1. Public Land Survey Sec 1 T 10 N R 3 W M-3, SE Corner  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, William Tingley a field survey on July 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

1831, Robert Clark, Jr., Deputy Surveyor, page 293, GLO Notes

Set Post

Sugar 8" S21-1/2°W 52 links

Sugar 15" N68°W 10 links

1871, D.W. Altenburg, County Surveyor, Liber B, Page 57, Record of Minutes of Survey, Gratiot County Records

Old Corner Found, Stone Corner

Sugar 16" N52°W 55 links

Beech 8" S54-1/4°E 78 links

1871, D.W. Altenburg, County Surveyor, Liber B, page 48

Shows Corner 14 links South of Southwest Corner, Section 6, T10N, R2W

1894, D.W. Altenburg, Liber B, Page 57

Stone Corner

Post 8" S58-1/2°E 55 links

Post 10" S60-1/2°W 60 links

1967, Survey of SW 1/4 of Section 1, by Merrill Hunter

No Corner Monument Described (9.24' South of Southwest corner of Section 6, North Star Township

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" Iron Pipe 1 foot long

Below Pipe 2 feet deep, found large stone (10 pounds)

Found below stone, another stone at 2.8 feet deep with old logging chaining wrapped around it.

Below Second stone found woodstake 2" x 2" round

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Remonumentation Corner over Wood Stake

Found Nail and Tag in Power Pole S50°E 61.0 feet

Found Nail and Tag in Power Pole S35°W 88.22 feet

Found Nail and Tag in Power Pole N35°W 60.00 feet

Set Nail and Tag in 6" Elm N45°E 81.09 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-12-1995

Surveyor's Michigan License No. 30104

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95

*WGT*  
William Tingley, PS, Chairman

