

APR 23 1999

GRATIOT COUNTY REMONUMENTATION PROGRAM

LIBER 605 PAGE 839

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH. RECORDED

'99 APR 27 AM 8 34

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION

Form with fields for Gratiot (County), Located In: Township, Corner Code #, and numbered items 1-5.

Grid table with columns A-M and rows 1-13.

I, William G. Tingley, in a field survey on 19... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831, Joel Wright, G.L.O. Notes Intersect N. boundary at end of 5 miles (no witnesses given)

1852, Austin Burt, G.L.O. Notes Intersect W. boundary at end of 5 miles Beech 12 N8 W13 Beech 8 S45 E25

Sept. 1872 D.W.A., Field Book Stone marked T.C. Stone S52 W. 71 1/4 Stone N45 W. 60 o.c.f.

Oct. 1876, D.W.A., Field Book Stone 8x10x24 mr T.C. Stone S52 W 71 1/4 Stone N45 W. 60 Post 12 N 40 E. 37 3/4 Post 10 S 34 3/4 E. 57 1/2

Oct. 1876, D.W.A., Record of Minutes of Survey, Liber B, Page 228 (Stone on Top) Stone cor. T.C. 8"x10"x24" Stone S 52° W 71 1/4 Stone N 45° W 60

D.W.A., Record of Minutes of Survey, Liber A, Page 272, Liber B, Page 119 Stone Cor 8"x10"x24" Stone S52° W. 71 Post 12 N 40° E 37 3/4 Post 10 S 34 3/4 E. 57

May 1892, D.W.A., Record of Minutes of Survey, Liber C, Page 203 Stone Cor. 8"x10"x24" T.C. Stone S. 52°W. 71 1/4 Stone N. 45°W. 60

1892, D.W.A., Record of Minutes of Survey, Liber B, Page 107 Stone cor T.C. Stone South 52°W 71 1/4 Stone N 45° W. 60

August 12, 1996, Mark L. VanRaemdonck, Recorded Survey, Liber 561, Page 1429 Pipe in Monument Box S30°W 66.43' N&T #24622 N. face util. pole N60°E 41.58' N & T #19003 Se face util. pole N35°W 33.05' N. end 18" CMP East 3.30' Centerline road N&T N. Sd PP 110° Az. 121.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1"x1' iron pipe in monbox over stone and bits of clay tile. Found Nail & Tag #19003 south side power pole N60°E 41.70 Feet Found Nail & Tag #30104 north side power pole S70°E 120.59 Feet Found Nail & Tag #24622 north side power pole S35°W 66.38 Feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Remonumentation corner between stones and over bits of clay tile. Found Nail & Tag #19003 south side power pole N60°E 41.70 Feet Found Nail & Tag #30104 north side power pole S70°E 120.59 Feet Found Nail & Tag #24622 north side power pole S35°W 66.38 Feet Center of catch basin N40°W 40.33 Feet


This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 3/15/98

Surveyor's Michigan License No. 30104

ACCEPTED BY THE GRATIOT COUNTY SURVEYOR GROUP AS THE OFFICIAL CORNER UNDER PUBLIC ACT 345 OF 1990 AT A MEETING HELD 3/15/98

William Tingley, PS, Chairman



LIBER 5 PAGE 113

383