

FEB 22 1996

GRATIOT COUNTY REMONUMENTATION PROGRAM

GRATIOT CO. MICH.

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

RECORDED

Filing Requirement of Act 74, Mich. P.A. 1970

'95 DEC 20 PM 1 28

Janet M. Davis REGISTER OF DEEDS

corners in
 Gratiot _____ Located In: _____ Corner Code # _____
 (County) New Haven Township

Public Land Survey Sec 31 T 10 N R 4 W A-13, SW Corner
 T _____ R _____
 T _____ R _____
 T _____ R _____

Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

Miscellaneous S _____ T _____ R _____

Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Tingley a field survey on June 30, 1995
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 recent manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

Description of original monument and accessories and/or subsequent restoration:

#31, Robert Clark, Jr., Deputy Surveyor, GLO Notes

West on South Boundary, Section 31, T10N-R5W

75.50 chains - Intersect West boundary of the end of 5 miles 79 chains, 16 links

Sugar 16" S42-1/2°E 25 links

Sugar 14" N21-1/2°E 21 links

North on East Boundary Section 1, T9N-R5W, 79.16 chains - Intersect North Boundary at end of 5 miles

75 chains, 50 links

#69, D.W. Altenburg, Gratiot County Surveyor, Liber B, Page 16, Record of Minutes of Survey

Post 3" x 3"

Pine Stump 40" N32-1/2°E 50 links

Beech 16" S40-1/2°E 61 links

#91, Edward Jones, County Surveyor

Pine Stump 42" N25-1/4°E 76 links

Pine Stump 42" S66°E 102 links

#95, R.D. McNutt, County Surveyor, Record Cards

Found stone

Double Wild Cherry Southeast 47.0 feet

#98, Salisbury and Saunders, Surveyors in Consumers Power Company Survey

Found stone

28" White oak S55°E 28.4 feet

Telephone Pole S45°W 40.8 feet

Telephone Pole N45°W 90.7 feet

#975, Montcalm County Road Commission

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found rered at surface

Found 3/4" pipe below rered

Found stone on Eastside of rered (point end up 0.8' x 0.8' x 1.3')

Found crockery around stone

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation corner in place of stone (left stone beside)

Found nail in Power Pole S35°W 89.25 feet

Found nail in 23" Hickory S30°E 90.37 feet

Centerline of 3" Oak N55°E 90.40 feet

Top, Center of Cable Riser Box West 24.95 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-22-1995

Surveyor's Michigan License No. 30104

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER
 GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95

WGT.
 William Tingley, PS, Chairman

