

GRATIOT COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH.  
RECORDED

'95 DEC 20 PM 1 28

For corners in Gratiot Located In: New Haven Township Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey Sec 31 T 10 N R 4 W A-13, SW Corner  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Janet M. Davis*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on June 30, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes

West on South Boundary, Section 31, T10N-R5W  
75.50 chains - intersect West boundary of the end of 5 miles 79 chains, 16 links  
Sugar 16" S42-1/2°E 25 links  
Sugar 14" N21-1/2°E 21 links

North on East Boundary Section 1, T9N-R5W, 79.16 chains - Intersect North Boundary at end of 5 miles  
75 chains, 50 links

1869, D.W. Altenburg, Gratiot County Surveyor, Liber B, Page 16, Record of Minutes of Survey

Post 3" x 3"  
Pine Stump 40" N32-1/2°E 50 links  
Beech 16" S40-1/2°E 61 links

1891, Edward Jones, County Surveyor  
Pine Stump 42" N25-1/4°E 76 links  
Pine Stump 42" S66°E 102 links

1935, R.D. McNutt, County Surveyor, Record Cards

und stone  
ouble Wild Cherry Southeast 47.0 feet

1968, Salisbury and Saunders, Surveyors in Consumers Power Company Survey

Found stone  
28" White oak S55°E 28.4 feet  
Telephone Pole S45°W 40.8 feet  
Telephone Pole N45°W 90.7 feet

1975, Montcalm County Road Commission

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found rerod at surface  
Found 3/4" pipe below rerod  
Found stone on Eastside of rerod (point end up 0.8' x 0.8' x 1.3')  
Found crockery around stone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation corner in place of stone (left stone beside)  
Found nail in Power Pole S35°W 89.25 feet  
Found nail in 23" Hickory S30°E 90.37 feet  
Centerline of 3" Oak N55°E 90.40 feet  
Top, Center of Cable Riser Box West 24.95 feet

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95

WGT.  
William Tingley, PS, Chairman



This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-22-1995

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1983

SURVEY &  
REMONUMENTATION