

NOV 16 2000

GRATIOT COUNTY REMONUMENTATION PROGRAM

GRATIOT CO. MICH. RECORDED

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'98 DEC 22 AM 10 53

SECTION

For corners in

	Located In:		Corner Code #
	Gratiot	Township	
1. Public Land Survey	T 10N R 4W	E-i NW Corner	
	T R		
	T R		
	T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley, in a field survey on October 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

December 6, 1831, Orange Risdon, Deputy Surveyor
Intersected North Boundary 407 links (268.62 or feet) West of quarter section post.
Set corner post sections 4 and 5

Beech 12" S70°E 14 links
Beech 10" S79°W 16 links

May 1874, D.W. Attenburg, County Surveyor, book B, page 37 from Record of Minutes of Surveys at Gratiot County Drain Commission.
Set 3"x3" post

Pine 36" N34°E 137¼ links
Forked apple 4" N4½°W 97½ links

July 2nd, 1981, John Nelson #21273, recorded L.C.R.C. Liber 2, Page 27.

Set 5/8" roerod with RLS cap on township line 1.0' north of the centerline of Washington Road, and in the centerline of Osborn Road, by extending the west line of section 4 0.75' northerly through a found PK nail.

Found nail with R.L.S. tag in S.W. side of 14" box elder Az.123° 91.97'
Found nail with bottle cap in northeast side of telephone pole Az.155° 53.94'
Found nail with R.L.S. tag in side of utility pole Az.212° 66.16'
S1/4 cor. Sec. 33 - 11 - 4 East 268.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" roerod in ¾" pipe with registered land surveyors cap #21273 in a mon box 1.0 feet north of the centerline of county road 555, 268.10 feet west of F13 of T11N-R4W, agreeing closely with original notes' 407 links (or 268.62 feet)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Remonumentation corner and monument box 1.0 feet north of the centerline of county road 555 in place of the 5/8" roerod

Nail and tag in the southwest side of a 14" Box Elder S57°E 91.97 feet
Nail and tag in the northeast sided of a telephone pole S25°E 53.97 feet
Nail and tag in the east side of a utility pole S32°W 66.16 feet
F13 of T11N-R4W East 268.10 feet
Center of a telephone cable box N40°E 44.65 feet

ACCEPTED BY THE GRATIOT COUNTY SURVEY DEPT GROUP AS THE OFFICIAL CORNER UNDER PUBLIC ACT 345 OF 1990 AT A MEETING HELD 3/18/98

WGT
William Tingley, PS, Chairman

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 3/18/98

Surveyor's Michigan License No. 30104

man set

384

LIBER 598 PAGE 1280