

GRATIOT COUNTY REMONUMENTATION PROGRAM GRATIOT CO. MICH.
LAND CORNER RECORDATION CERTIFICATE RECORDED
 Filing Requirement of Act 74, Mich. P.A. 1970 **97 DEC 29 AM 9 37**

For corners in Gratiot Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey Sec 36 T 11N R 2W
 T 11N R 1W M-13, SE Corner
 T R A-13, SW Corner
 T R
 T R

2. Property Controlling in Section S T R
 S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Janet M. Davis
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on January 15th, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
 62.27 Chain; intersected line between Range 1 and 2 West at end of 5 miles, 79 chains, 55 links at 45 links South of temporary post
 80 chains Set Post Corner T11N- 1 and 2 West
 Elm 30" N54°E 35 links
 Beech 10" N50-1/2°W 43 links
- 1873, D.W. Altenburg, County Surveyor, Liber B, Page 117 and Field Book 11-2, Pages 168 and 169
 2" x 2" Post - old corner found
 Elm 10" N54-1/2°E 108 links
 Oak 36" S20°E 180-1/2 links
- 1882, D.W. Altenburg, County Surveyor, Field Book 11-2, page 168 and 169
 Stone Corner
 Norway Maple 2" Southeast 30.7 feet
 Norway Maple 2" Southwest 37.2 feet
 Fence Post Northeast 60.0 feet
- 1968, Field Book, 11-2, Page 168 - no surveyor shown
 Set Monument Box at Corner
 No date, County Road Commission records
 Monument Box
 Nail and Cap in Ash Northeast 43.88 feet
 Nail and Cap in Box Elder Northwest 31.95 feet
- 1975, D.B. Whittier, LCRC, Liber 1, Page 355
 Found pipe in monument box
 Nail and Tag in Telephone Pole N45°W 72.0 feet
 Nail and Tag in East side Telephone Pole S45°E 37 feet
 West Leg of Stop Sign Northeast 55.5 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11/19/97

WGT.
 William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe in Monument Box at surface. At 1.5 feet +/- below surface, found a large stone with stones around

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Monument over 3/4" Pipe in Monument Box.
- 16 d Spike in Westside Power Pole N40°W 72.21 feet
- 16 d Spike in Northside Power Pole S55°W 72.69 feet
- 16 d Spike in South side Power Pole S35°E 82.29 feet
- West Leg of Stop Sign N40°E 52.83 feet



This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 11/19
 Surveyor's Michigan License No. 30104

