

MAY 05 1997

GRATIOT COUNTY REMONUMENTATION PROGRAM

GRATIOT CO. MICH. RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'96 NOV 26 PM 2 33

For corners in Gratiot Located In: Corner Code #
 (County) Lafayette

1. Public Land Survey Sec 31/ T 11N R 1W C-13, S. Bdry
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field survey on December 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
 Set Post Corner Sections 31 and 32
 Black Ash 7" N33°E 36 links
 Lynn 10" N60°W 49 links
 No Date, Field Book 11-1, Pages 80-81
 Stone
 Elm 4" N60-1/2°W 89 links
 1880, S.S. Hastings, County Surveyor, Field Book 11-1, Pages 78 and 79
 Stone 8" x 12" x 30" and stones around - old corner found
 Oak 50" S9-1/2°E 76 links
 Shows 1.70 chain jog to Corner of 5 & 6 T10N-R1W
 Also recorded on page 78
 1961, County Road Plans Sta. 31+32 5.76 North of P.I.
 July 19, 1968 - Found old corner and set monument box
 No date, no surveyor, County Road Commission Record
 Monument Box
 Nail in Southside Power Pole Northeast 55.60 feet
 Nail in Southside Power Pole West Northwest 66.32 feet
 P.K. Nail 5.76 feet South and 2.78 feet West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Iron Pipe in Monument Box over a 1" Solid Shaft. 1" Solid on North Edge of Large Stone at 2 feet below surface. Accepted 1" Solid at High Edge of Stone. 111.90 feet East of Corner 6-5 T10N-R1W 6 feet North of Centerline of pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set Remonumentation Monument over Stone
 Top Center of 48 foot CMP Culvert S35°W 35.5 feet
 Found Spike in south Face of Power Pole N45°E 55.5 feet
 Centerline East Leg of Arrow Sign S05°E 39.20 feet
 Center Steel Post (Telephone Cable Marker) S40°W 85.21 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 10/15, 1996.

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993



ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/27/96

WGT.
William Tingley, PS, Chairman