

GRATIOT COUNTY REMONUMENTATION PROGRAM

GRATIOT CO. MICH.  
RECORDED

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'96 NOV 26 PM 2 33

COMMISSION

For corners in

Located In:

Corner Code #

Gratiot  
(County)

Lafayette

- |                                    |        |       |      |            |
|------------------------------------|--------|-------|------|------------|
| 1. Public Land Survey              | Sec 32 | T 11N | R 1W | D-13, S1/4 |
|                                    |        | T     | R    |            |
|                                    |        | T     | R    |            |
|                                    |        | T     | R    |            |
| 2. Property Controlling in Section | S      | T     | R    |            |
|                                    | S      | T     | R    |            |
| 3. Miscellaneous Property in Sec.  | S      | T     | R    |            |
|                                    | S      | T     | R    |            |

*Janet M. Davis*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Tingley a field survey on December 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes

Set 1/4 Section Post

Sugar 7" N82-1/2°E 17 links  
Lynn 8" N87°W 24 links

No date, Field Book 11-1, Pages 80 and 81

4" x 4" Oak Post

Elm 3" N60°E 94 links  
Elm 2" N34-1/2°W 59 links

Also on page 81, Found Stone, set 3/4" pipe 2 feet long

No date, probably D.B. Whittier from Road Commission Record

Found Stone, removed stone and set 3/4" pipe 2 feet long

Hub and nail by post North 46.25 feet  
Nail and Washer in Telephone Pole South 29.77 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 1.3 feet long Iron Pipe in Monument Box. At 1.5 feet below surface found another 3/4" Pipe with 3/4" hex bar in top. Dug 1.8 feet +/- in Grey Clay undisturbed subsoil. Accepted as Whittier 3/4" pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over Iron Pipe 79.75 East of North 1/4 Corner, Section 5, T10N-R1W.

Nail & Tag in Cedar Fence Post North 38.98 feet  
Bolt Through Wood Post (Electric Box) S50°E 74.45 feet  
Found Nail & Tag in Power Pole N45°E 76.35 feet  
Centerline Cable Riser Box S70°W 136.30 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 10/15, 1996


Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1993



ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/15/96

WGT  
William Tingley, PS, Chairman