

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'96 NOV 26 PM 2 33

COMMISSION

For corners in Gratiot Located In: Lafayette Corner Code # _____
 (County)

1. Public Land Survey Sec 33/T 11N R 1W G-13, S. Bndry
 34 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Tingley a field survey on December 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
 Set Post Corner Sections 33 and 34
 Elm 11" N09°E 12 links
 Beech 12" N70°W 28 links
- 1876, D.W. Altenburg, County Surveyor, Field Book 1, Pages 82 and 83
 Post 2" x 2" - old corner found
 Swamp Elm 20" N40-3/4°E 76 links
 Stone 10" S55°W 57-1/4 links
 14 links (9.24 feet) East of 3 & 4, T10R-R1W
- 1995, Gratiot County Road Commission
 Found Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 3/4" Bar in Monument Box. 8.65 feet East of 3/4" Rod in Monument Box.
 Dug 3 feet deep into Clay, no further evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Monument over 3/4" Bar in Monument Box.
 Found Nail in Power Pole N45°W 42.41 feet
 Set Nail & Tag in Power Pole S45°E 39.73 feet
 Set Nail & Tag in Power Pole S45°W 44.40 feet
 Northeast Corner House Foundation S50°W 75.86 feet

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Signed by William G. Tingley Date 10/15, 1996
 Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/15/96

WGT
 William Tingley, PS, Chairman

