

**SURVEY & REMONUMENTATION** **GRATIOT COUNTY REMONUMENTATION PROGRAM**

LIBER **562** PAGE **1314**

GRATIOT CO. MICH.  
RECORDED

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

'96 NOV 26 PM 2 34

*Janet M. Davis*  
REGISTER OF DEEDS

For corners in Gratiot (County) Located In: Emerson Corner Code # \_\_\_\_\_

1. Public Land Survey Sec 19 T 11N R 2W A-8, W 1/4  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

William Tingley a field survey on September 5, 1995.  
 I do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not Set GLO  
 1862, S.S. Hastings, County Surveyor, Liber A, Page 19, Record of Minutes of Survey  
 1" Pipe 30" long at 20 links East of Section line and 40 chains North of South line  
 1984, Jan S. Fokens, #21567, Survey, Liber 469, Page 883

Found Monument Box

Center Jog Corner, Monument Box South 46.78 feet  
 Nail & Cap Corner Fence Post East 43.20 feet  
 Nail & Cap Dead Elm S15°W 100.73 feet  
 Nail & Cap 30" Oak S15°E 121.18 feet

1995, Gratiot County Road Commission

State Road Project A H59DOA  
 Found Tee Iron 2 feet deep 47 feet North of Pointed Stone (M-8 T11N-R3W)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Tee Iron 2 feet deep. 47 feet North of M-8 (11-3)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over "T" Iron in Monument Box

Found Nail & Tag in Corner Fence Post S80°E 43.28 feet  
 Found Nail & Tag Westside 35" White Oak S40°E 120.78 feet  
 Found Nail & Tag Eastside 10" Elm S30°W 111.07 feet  
 Steel Fence Post (3rd North of Corner) S80°W 36.41 feet

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Signed by William Tingley Date 10/15, 1996  
 Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 ADAPTED FOR WORD PROCESSING MARCH, 1993

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/15/96

WGT  
 William Tingley, PS, Chairman