

SURVEY & REMONUMENTATION

GRATIOT COUNTY REMONUMENTATION PROGRAM

LIBER **538** PAGE **507**

AUG 31 1994 Corner approved by Peer Group on _____, 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Gratiot</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Sec 32 T <u>11</u> R <u>2</u>	<u>C-11, NW Corner</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

GRATIOT CO. MICH.
RECORDED
'94 AUG 19 AM 10 08

Janet M. Davis
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field survey on July 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1880, GLO Notes
Set Post
White Ash 10" S47°W 30 links
Yellow Birch 12" N46°E 21 links
January 1862, S.S. Hastings, County Surveyor, Liber B Page 161
Post and stones promised
January 1880, T.H. Harrod, Surveyor, Liber B, Page 297
New corner and axe buried
Large stone N43°E 83-1/2 links
Gratiot County Road Commission Record of Minutes of Survey
C.B. Fraker in 1867 and others since (dates not recorded)
Stone corner
Walnut 4" N39°W 68 links
Oak Post 12" S38-1/2°E 61-3/4 links
May, 1976, Donald E. Hunter, #19177, recorded survey, Liber 402, Page 1063
Nail in Northside Telephone Pole S45°E 40.5 feet
Nail and Tag in Northwest side Telephone Pole N45°E 41.67 feet
Nail in Northeast side tree N45°W 44.95 feet
June, 1985, Jan S. Fokens #21567, recorded survey, Liber 469 Page 885
Found gear and shaft
Nail and cap 18" Walnut Northwest 44.9 feet
Michigan State Highway Dept. Tag in Pole Northeast 41.64 feet
Scaffolding Nail & Flag Southeast 40.55 feet
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Gear and Shaft .8 feet deep in nest of stones
Found 4" Walnut (with nail, now 15") N39°W 44.91 feet
Found Axe Head 1.8 feet deep
Found Nail & Tag Eastside Power Pole N43°W 71.01 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner and Monument Box.
Found Nail Eastside 15" Walnut N39°W 44.91 feet
Found Nail and Tag Eastside Power Pole N43°W 71.01 feet
Northwest Corner Riser Box S50°E 39.14 feet
Dead End Road Sign S15°W 49.85 feet
Buried Cable Marker N50°E 45.09 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

William Tingley 5 Aug 94

Surveyor's Michigan License No. 30104

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEE GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 5 Aug 94
William Tingley
William Tingley, PS, Chairman

