

SURVEY & REMONUMENTATION

LIBER **562** PAGE **1313**

MAY 05 1997

GRATIOT COUNTY REMONUMENTATION PROGRAM

GRATIOT CO. MICH.

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

RECORDED

Filing Requirement of Act 74, Mich. P.A. 1970

'96 NOV 26 PM 2 34

Janet M. Davis
REGISTER OF DEEDS

For corners in _____ Located In: _____ Corner Code # _____
 _____ (County) Emerson _____

1. Public Land Survey Sec 32 T 11N R 2W _____ D-13, S 1/4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on November 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1831, Robert Clarke, jr., Deputy Surveyor, GLO Notes Elm 19" for quarter section post
- 1880, T.H. Harrod, Deputy Surveyor Ironwood 2" x 2"
- 1989 William Ruddell, Survey, Liber 495, Page 370 Set Masonry Nail & Tag
- Nail and Cap In Southwest side Power Pole N45°W 54.50 feet
- Nail and Cap in Southwest side Stub Power Pole N20°E 49.20 feet
- P.K. and Cap in Northwest side Power Pole S34°W 90.63 feet
- Northwest Corner church Planter Box Southeast 68.44 feet
- Road Centerline South 0.70 feet

1990, William Ruddell, Survey, Liber 495, Page 1340

Same as Liber 495, Page 470

1995, Gratiot County Road Commission

Found silver surveyor's tag #14769

1995, W.G. Tingley #30104, Survey #95181

Found Iron and Cap #14769

- Found Nail & Tag #14769 in Power Pole S45°W 90.63 feet
- Found Nail & Tag #14769 in Power Pole N30°W 54.47 feet
- Northeast Corner Brick Sign Foundation S45°E 71.43 feet
- Top Center 36" Corrugated Metal Pipe N05°W 33.28 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Nail and Cap #14769. Dug through concrete pavement, found no other monument. Set 3/4" pipe in Monument Box in place of Nail and Cap. 2641.73 feet East of C-13 (Ruddell) and 2641.89' West of E-13 (Tingley record).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner over 3/4" Pipe.

- Found Nail & Tag #14769 in Power Pole S45°W 90.63 feet
- Found Nail & Tag #14769 in Power Pole N30°W 54.47 feet
- Northeast Corner Brick Sign Foundation S45°E 71.43 feet
- Top Center 36" Corrugated Metal Pipe N05°W 33.28 feet

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Signed by William G. Tingley Date 10/15 1996

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/15/96

WGT
William Tingley, PS, Chairman