

JAN 20 2000

GRATIOT COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
GRATIOT COUNTY
RECORDED

11 JAN 2000 9:37 A.M.

JANET K. DAVIS
REGISTER OF DEEDS

SECTION

For corners in

| | | |
|---------------------------------------|-------------------------|-----------------|
| Gratiot (County) | Located In: | Corner Code # |
| | Emerson | |
| 1. Public Land Survey | Sec 32 T 11N R 2W | E-13, Sec. Cor. |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, William Tingley a field survey on June 28, 1995
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
Set Post Corner Sections 32 and 33
Sugar 6" N64°E 26 links
Hickory 13" N20°W 19 links
- 1880, T.H. Harrod, County Surveyor, Field Book 11-2, pages 160-163
Oak 4" x4" - Old Corner Found
Elm 36" S82°W 81 links
- Liber B, Page 297, Record of Minutes of Survey
Same record
- 1955, Michigan State Highway Department, Project 29-17, J. Dykstra, Project Engineer
Corner obliterated - reset by proportional measurement - 3/4" Iron form pin flush with pavement surface -
6.20 feet North of Centerline of existing 22 foot bituminous concrete pavement.
Chiseled "X" on culvert headwall N29°W 33.65 feet
Power Pole N33°W 47.78 feet
Telephone Pole S56°W 86.60 feet
19" Maple N71°W 84.30 feet

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/15/96

William Tingley
William Tingley, PS, Chairman

- 1972, D.B. Whittier, LCRC, Liber 1, Page 281
Found 3/4" Iron Bar approximately 2" below surface
Center of catch basin N52°W 72.69 feet
Center of catch basin N40°E 46.78 feet
Center of catch basin S60°W 73.48 feet
- 1972, M. Hunter #1470, Survey, Liber 1, Page 149
Same as LCRC, Liber 1, Page 281
- 1995, W.G. Tingley
Found 1" Solid Iron, located 6.2 feet North of Centerline Road
Found Nail and Tag #14769 in Power Pole N45°W 50.14 feet
Found Nail and Tag #14769 in Power Pole S45°W 96.73 feet
Top Center Catch Basin N28°E 46.87 feet
Top Center Corrugated Metal Pipe S55°E 66.46 feet



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Iron Bar in Monument Box 6.2 feet North of Centerline of Washington Road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner over 3/4" Iron Rod.
Found Nail and Tag #14769 in Power Pole N45°W 50.14 feet
Found Nail and Tag #14769 in Power Pole S45°W 96.73 feet
Top Center Catch Basin N28°E 46.87 feet
Top Center Corrugated Metal Pipe - East end S55°E 66.46 feet

This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by William Tingley Date Oct 15, 1996

Surveyor's Michigan License No. 30104