

GRATIOT COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

MAY 05 1997

GRATIOT CO. MICH. RECORDED

'96 NOV 26 PM 2 35

COMMISSION

For corners in

Gratiot

(County)

Located In:

Emerson

Corner Code #

- 1. Public Land Survey Sec 33 T 11N R 2W F-13, S 1/4
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

Janet M. Davis REGISTER OF DEEDS

- 4. Lot No. Recorded Plat
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on November 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1832, Robert Clarke, Jr., Deputy Surveyor, GLO Notes

Set Quarter Section Post

- Beech 7" N45°E 38 links
- Beech 9" N35°W 46 links

1880, T.H. Harrod, County Surveyor, Field Book 11-2, pages 162 and 163

Oak 3" x 3"

- Beech 14" S46-1/2°W 57 links
- Black Ash 14" S44-1/4°E 68-1/2 links

1955, Michigan State Highway Department, Project 29-17, J. Dykstra, Project Engineer

Found 2" square Oak Stake with large boulder alongside, buried 8", Set 3 feet of 1-1/2 inch diameter axle shaft top buried 8 inches (2 feet North of centerline, 25 feet blacktop road)

- 20" Bitternut S76°30'W 98.39 feet
- 16" Maple N65°30'W 73.97 feet
- 23" Maple N05°30'W 29.16 feet
- 11" Elm N06°30'E 56.03 feet

1972, D.B. Whittier #10070, LCRC, Liber 1, Page 281

Found axle shaft, brought to surface with 3/4" pipe and set Monument Box. Same bearing trees as 1955 above.

1972, D.B. Whittier #10070, Survey, Liber 1, Page 149

Found axle, raised to surface with 3/4" pipe and set Monument Box.

1979, W.B. Ruddell, LCRC, Liber 4, Page 499

Found pipe in Monument Box

- Nail and Flag in 24" Maple North 29.15 feet
- Nail and Flag in Power Pole Northwest 72.48 feet
- Nail and Flag in 24" Elm West Southwest 98.4 feet

1981, T.J. Mueller, #25861, Survey, Liber 595, page 1233

Same as LCRC, Liber 1, Page 499

Continued on Back.....

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pin Monument Box over axle shaft 1.3 feet deep.

- 26" Bitternut Hickory (identified as Elm and Ash by Ruddell) S70°W 98.40 feet
- 23" Maple (now 26" Maple) N05°W 29.15 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner over axle shaft.


- Nail and Tag 26" Maple North 29.15 feet
- Nail and Tag Power Pole Northwest 72.48 feet
- Nail and Tag 26" Bitternut Hickory (previously identified as Elm and Ash) West Southwest 98.4 feet
- Top Center Dome on Catch Basin Northeast 38.5 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley

Date 10/15 1996

Surveyor's Michigan License No.



ACCEPTED BY THE GRATIOT COUNTY BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISIED MAY 14, 1975 REVISIED JAN., 1983 PUBLIC ACT 345 OF 1990 AT A MEETING HELD AT GRAND MARSH, MICHIGAN, MARCH, 1993

WGT William Tingley, PS, Chairman

1991, W. Ruddell, LCRC, Liber 2, Page 295 and Liber 595, Page 716

Pipe in Monument Box		
Nail and Tag 26" Maple	North	29.15 feet
Nail and Tag Power Pole	Northwest	72.48 feet
Nail and Tag 26" Ash (previously identified as Elm)	West southwest	98.4 feet
Top Center Dome on Catch Basin	Northeast	38.5 feet