

SURVEY & REMONUMENTATION

LIBER **563** PAGE **1119**

GRATIOT COUNTY REMONUMENTATION PROGRAM

SEP 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH.
RECORDED

'96 DEC 26 AM 10 37

Janet M. Davis
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in **SECTION**

Gratiot (County) Located In: Emerson Township Corner Code #

1. Public Land Survey Sec 33 T 11N R 2W G-13, Sec Cor
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I William Tingley a field survey on November 20, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
Set Post Corner Sections 33 and 34
Beech 11" N54°E 20 links
Beech 8" N68°W 34 links
- 1880, T.H. Harrod, Deputy Surveyor
White Ash 2" x 4" Old Corner Found
Oak 2" N73°W 94 links (62.04 feet)
- 1955, Michigan State Highway Department, Project 29-7, J. Dykatra, Project Engineer
Found 1" Iron Shaft 8" below surface
Southwest Corner of 1 story frame house N79°30'E 331.5 feet
14" Cherry N21°30'E 138.43 feet
9" Cherry N66°E 117.78 feet
Telephone Pole S31°W 35.58 feet
- 1978, Gratiot County Road Commission
1" Iron Shaft in Monument Box
- 1979, W.B. Ruddell #14769, LCRC, Liber 1, Page 498
Found pipe in Monument Box
Telephone Pole Southeast 47.71 feet
West Leg on Sign South 17.6 feet
East Leg on Stop Sign Northwest 56.15 feet

ACCEPTED BY THE ~~MONTGOMERY~~ **GRATIOT** COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 12-17-96

W.T.
William Tingley, P.S., Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 1-1/4" Iron Pipe on top of 1" Steel Shaft between stones with crockery 12" deep on Centerline of Road North and on Centerline of East/West Road
Telephone Pole Southeast 47.71 feet


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner over Pipe and Shaft.
Found Tag #14769 and Nail in Power Pole S45°E 41.75 feet
Center of 3" Steel Post (7 foot high) S55°W 112.94 feet
Northeast Corner of North end Curb (Eastside Bagley Road North) N35°E 63.62 feet
Centerline leg on Arrow Sign (Street Sign) South 22.45 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 12-17, 1996

Surveyor's Michigan License No. 30104



1/17 File