

**SURVEY & REMONUMENTATION**

LIBER **562** PAGE **1312**

**GRATIOT COUNTY REMONUMENTATION PROGRAM**

**MAY 05 1997**

**LAND CORNER RECORDATION CERTIFICATE**

GRATIOT CO. MICH.  
RECORDED

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

96 NOV 26 PM 2 34

For corners in Gratiot Located In: \_\_\_\_\_ Corner Code \_\_\_\_\_

#	(County)	Emerson	Corner Code
1.	Public Land Survey	Sec 34 T <u>11N</u> R <u>2W</u>	<u>I-13, Sec. Corn</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2.	Property Controlling in Section	S _____ T _____ R _____	_____
		S _____ T _____ R _____	_____
3.	Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
		S _____ T _____ R _____	_____
4.	Lot No. _____	Recorded Plat _____	_____
5.	Private Claims	_____	_____

*Janet M. Davis*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field survey on December 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
  - Set Post Corner Sections 34 and 35
    - Elm 8" N29°W 27 links
    - Birch 7" N38-1/4°E 37 links
- 1880, T. H. Harrod, Deputy Surveyor, Field Book 11-2, Page 164 and 165 and Liber B, page 295, Record of Minutes of Survey
  - Maple 2" x 3" Old Corner found
  - Elm 24" S01°E 56 links
  - Black Ash 6" N43-1/2°E 63 links
  - Set pipe 1" x 36" cap

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- Found 3/4" Pipe in Monument Box 8 feet North of Centerline East-West Road and 10 feet West of Centerline of Gravel Road North. 10" deep found Guard Rail Bolt. Two feet deep found 3/4" Pipe with small stones around.
- I-13, 11-2 is 1217.25 feet West of I-1, T10N, R2W. Record is 1215.72 feet GLO.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Set Remonumentation Monument over 3/4" Pipe.
  - Set Nail and Tag in Telephone Pole S60°E 93.92 feet
  - Set Nail and Tag in Power Pole N45°W 96.37 feet
  - Centerline Top Cable Riser Box S50°W 83.90 feet
  - Centerline Top 30" CMP Culvert N40°E 49.70 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 10/15/96

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1982  
ADAPTED FOR WORD PROCESSING MARCH, 1993

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/15/96

WGT  
William Tingley, PS, Chairman

