

SURVEY & REMONUMENTATION

GRATIOT COUNTY REMONUMENTATION PROGRAM

LIBER **538** PAGE **508**

AUG 5 1994 Corner approved by Peer Group on _____, 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gratiot
(County)

Located In:

Corner Code #

- 1. Public Land Survey Sec 7 T 11 R 3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

B-5, S 1/4

SURVEY & REMONUMENTATION

AUG 31 1994

COMMISSION

**GRATIOT CO. MICH.
RECORDED**

'94 AUG 19 AM 10 09

Janet M. Davis
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on August 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

May 19, 1832, Hiram Burnham, Deputy Surveyor, GLO Notes

Set Post

- Butternut 6" S8°E 8 links
- Beech 8" N14°W 29 links

November 1880, S.S. Hasting, County Surveyor, Liber C Page 65

Long Stone with stones around it

November 1880, S.S. Hastings, County Surveyor, page 8, 9

Stone 3-1/2 feet long and stones around new corner

June 1887, Parker Merrill, County, County Surveyor, Liber C, Page 161

Large stone.

June, 1992, W. G. Tingley #30104, Survey

Found 3/4" Pipe

Location of Centerline Reid & Harrison

- Set Nail Power Pole N0°E 33.6 feet
- Set Nail Power Pole S40°W 155.5 feet
- West end 12" Corrugated Metal Pipe S45°E 44.2 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Iron Pipe in Mon Box.

1 foot below surface found large point stone

- Found Nail Westside power pole N30°E 33.75 feet
- Found Nail Eastside power pole S35°W 155.40 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner and Monument Box over stone.

- Found Nail Westside Power Pole N30°E 33.75 feet
- Found Nail Eastside Power Pole S35°W 155.40 feet
- Buried Pipeline Marker S50°E 68.77 feet
- Stop Sign Post S30°E 39.74 feet

This corner is accepted as a careful and faithful perpetuation of the position or the original corner.

Signed by William Tingley Date 5 Aug, 1994

Surveyor's Michigan License No. 30104

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD Aug 29
William Tingley
Chairman

