

GRATIOT COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH.  
RECORDED

'95 DEC 20 PM 1 27

Corner corners in  
Gratiot \_\_\_\_\_  
(County)

Located In: \_\_\_\_\_  
Arcada Township

Corner Code # \_\_\_\_\_

Public Land Survey Sec 1 T 11 N R 3 W M-2, E 1/4  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Janet M. Davis*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Tingley a field survey on September 20, 1995.  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

831, Robert Clark, Jr., Deputy Surveyor, GLO Notes

Set quarter Section Post

Lynn 12" S45°W 43 links  
Sugar 16" N10°W 12 links

897, J.W. Harrod, County Surveyor, Liber A, page 65, Record of Minutes of Survey

Post Corner (in box)

Sugar 5" S32-1/2°W 98 links  
Maple Stump Southeast 40.0 feet  
Maple 18" Southwest 65 feet

961, Resurface plans by Michigan State Highway Department using 1931 construction data

1/4 Post Corner

Stake West 25 feet  
18" Maple Southwest 65.0 feet  
Maple (stump) Southwest 40.0 feet

995 Gratiot County Road Commission, Road Plans, Federal Project #MSTP 9529 (002)

Iron in Monument Box Station 186+43

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument box 12.1 feet South of railroad spike by MDOT. Set 5/8" rod to raise - nothing below; on wood fence to West.  
Found Sugar 5" (now 26") S32-1/2°W 98 links (64.68 feet)

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over rod in Monument box

Found Nail & Tag (#25861) in Power Pole N60°W 32.97 feet  
Found Nail & Tag (#25861) in 26" Sugar Maple S45°W 65.13 feet (Old bearing tree of J.W. Harrod, 1897)  
Found Nail in Face of Power Pole N70°E 79.40 feet  
Southeast Corner Concrete Gutter N40°W 56.18 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-22, 1995  
Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1974

REVISED MAY 14, 1978

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1993

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95

W. Tingley  
William Tingley, PS, Chairman

COM. 272  
REMONUMENTATION

FEB 22 1996

COMMISSION