

GRATIOT COUNTY REMONUMENTATION PROGRAM  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH.  
 RECORDED

'95 DEC 20 PM 1 27

Number of corners in \_\_\_\_\_  
Gratiot  
 (County)

Located In: \_\_\_\_\_  
 Arcada Township

Corner Code # \_\_\_\_\_

Public Land Survey Sec 12 T 11 N R 3 W \_\_\_\_\_  
 M-4, E 1/4

T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Janet M. Davis*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

William Tingley a field survey on September 12, 1995

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

331, Robert Clark, Jr., Deputy Surveyor, GLO Notes

Set Quarter Section Post

Sugar 8" S28°W 33 links

Maple 18" N77°W 7 links

276, Donald Hunter #19177 in Survey #g-2158, Liber 402, Page 1065

Does not describe monument. Corner 2641.76 North of Southeast of Section 12 (monument box)

277, Donald Hunter #19177 in Survey G-2718, Liber 410, Page 926

Does not describe monument. Shows East 1/4 Section 12, T11N-R3W, being 3 feet south of W 1/4 Section 7, T11N-R2W

295, Gratiot County Road Commission, Federal Aid Plans, Fed Proj. No. MSTP 9529 (002), Station 133+70

1/4 Corner. Found Monument Box in Center of Road

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Centerline previous road West in Centerline of North-South pavement, found 1" Iron Shaft in Monument Box 3 feet South of 1" rebar

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner over 1" Iron Shaft in Monument Box

Found Nail and Tag (#25651) in Southside 14" Maple N60°E 52.73 feet

Found Nail and Tag (#25651) in Southwest side 10" Maple S45°E 69.00 feet

Found Nail and Tag (#22651) in Southwest side Power Pole N40°W 71.05 feet

Centerline North Mail Box Post (pipe) S45°W 39.75 feet

Closing corner A-4 North 3.09 feet

This corner is accepted as the best available evidence of the position of the original corner.

Signed by William G. Tingley Date 12/2, 1995

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1976  
 REVISED JAN. 1983  
 ADAPTED FOR WORD PROCESSING MARCH, 1993

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95

WGT  
 William Tingley, PS, Chairman

COMMISSION  
 REMONUMENTATION

FEB 22 1996

COMMISSION

