

GRATIOT COUNTY REMONUMENTATION PROGRAM

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE

GRATIOT CO. MICH. RECORDED

COMMISSIONER

Filing Requirement of Act 74, Mich. P.A. 1970

'96 NOV 26 PM 2 33

For corners in gratiot Located In: Corner Code

#	(County)	Arcada	Corner Code
1.	Public Land Survey	Sec 13 T <u>11N</u> R <u>3W</u>	<u>M-6, 1/4</u> Corner
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2.	Property Controlling in Section	S _____ T _____ R _____	_____
		S _____ T _____ R _____	_____
3.	Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
		S _____ T _____ R _____	_____

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Tingley a field survey on September 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes

Set Quarter Post

Pine 30" S29°W 73 links
White Oak 14" N71°W 29 links

1913, T.H. Harrod, County Surveyor, Liber A, page 92, Record of Minutes of Survey in County Drain Commissioners Office
Plow shoe, set 26 links South of Emerson corner.

1961, Michigan State Highway Department Resurfacing Plans - Using 1931 Construction Plans
Arcada 1/4 Corner Station 158+41.24 (17.16 South of Emerson Corner)

1977, David Whittier #10070, Survey Liber 409, page 346

No East 1/4 Corner for Arcada Township. 1/4 Corner of Emerson Township is 1" pipe raised with 3/8" rod in monument box

1985, Jan Fokens #21567, Survey, Liber 469, Page 886

Shows Corner 17.16 feet South of Emerson Corner

No Corner description

1993, William Ruddell #14769, Survey Liber 526, page 1298

Set Nail and Cap in Pavement

West 1/4 corner, Section 18, T11N-R2W

Rod in Pipe in Monument Box	North	17.16 feet
Nail and Cap in Power Pole	South Southwest	133.75 feet
Nail and Cap 20" Spruce	East Southeast	73.75 feet
Capped "T" Iron	West	50.00 feet

1993, W. Ruddell, LCRC, Liber 2, Page 317

Same data as Survey, Liber 526, Page 1298

1995, Gratiot County Road Commission Road Plans, Federal Project MSTP 9529 (002)

Section Corner Station 80+82.84

In place at last resurfacing

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 3/4" pipe in Monument Box. Nothing else found. Pipe is 17.16 feet South of Emerson Corner per Harrod 1913, and Highway 1931.

Found Ruddell Power Pole South Southwest 133.75 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over 3/4" Pipe in Monument Box.

Set Nail and Tag in Corner Cedar Fence Post	S85°W	34.30 feet
Northerly Buried Cable Marker (Steel Post)	N50°E	38.17 feet
Set Nail and Tag in Southside 12" Twin Maple	N75°W	37.82 feet
Set Nail and Tag in Westside 18" Sugar Maple	N30°W	140.60 feet



This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Signed by William G. Tingley

Date 10/15/96

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/27/96

REVISED MAY 14, 1975
REVISED JAN., 1983
FOR WORD PROCESSING MARCH, 1993