

SURVEY & REMONUMENTATION

LIBER **562** PAGE **1302**

GRATIOT COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE

GRATIOT CO. MICH.
 RECORDED

MAY 05 1997

Filing Requirement of Act 74, Mich. P.A. 1970 NOV 26 PM 2 33

COMMISSION

For corners in Gratiot Located In: Arcada Corner Code # _____
 (County)

1. Public Land Survey Sec 24 T 11N R 3W M-8, E 1/4 Cor
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Janet M. Davis
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on July 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
 Set Quarter Section Post
 White Oak 6" S17-1/2°W 30 links
 Black Ash 10" N63°W 46 links
- 1880, T.H. Harrod, County Surveyor
 Oak Post 3" x 5" under stone
 Red Oak 30" N54-1/2°E 72-1/2 links
 Red Oak 30" N25-1/2°E 101 links
- 1980, T.H. Mueller #25861 in Survey Liber 436, Page 1260
 Found Wood Stake in Monument Box
 Corner fence post Northeast 47.99 feet
 24" Oak South southeast 76.69 feet
 East most sign post West 39.12 feet
 5" elm Southwest 59.08 feet



ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/15/96

WGT.
 William Tingley, PS, Chairman

- 1980, T.H. Mueller in LCRC, Liber 1, Page 522
 Records same data as Survey, Liber 436, Page 1260
- 1993, G. Gray, LCRC, Liber 2, page 222
 Found pointed rock in Monument Box
 32" White Oak 161 az 75.91 feet
 Corner Fence Post 52 az 58.31 feet
 Billboard Post 267 az 38.57 feet
 Monument Box 4 az 46.96 feet

1995, Gratiot County Road Commission, Federal Project #MSTP 9529 (002), Station 28+01, 1/4 Corner
 Monument Box with Tee Iron
 Construction P.I. 2.4 feet right

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found pointed stone two feet below surface 47 feet South Emerson Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Monument in Monument Box over Stone.
 Found a Nail & Tag in Corner Fence Post N45°E 58.31 feet
 Found a Nail & Tag Westside 35" White Oak S35°E 75.99 feet
 Street fence post 3rd North from Corner N45°W 52.30 feet
 Found Nail & Tag in Southside Wood Sign Post S85°W 38.50 feet
 Set Nail & Tag in Eastside 10" Elm S45°W 68.05 feet
 Located 2 feet North of extension of old fence West

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 10/15/1996

Surveyor's Michigan License No. 30104