

SURVEY & REMONUMENTATION

AUG 31 1994

COMMISSION

GRATIOT COUNTY REMONUMENTATION PROGRAM

LIBER 538

PAGE 506

Corner approved by Peer Group on 5 Aug, 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Gratiot Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey Sec 6 T 11 R 4 A-1, NW Corner
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

GRATIOT CO. MICH.
RECORDED

'94 AUG 19 AM 10 08

Janet M. Davis
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field survey on July 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1831, Roger Clarke, Jr., Deputy Surveyor, GLO Notes
 Set Post
 Beech 10" N45°E 28 links
 Elm 17" S24°W 8 links
 May 1879, S.S. Hastings, County Surveyor, Liber C, Page 29
 Cedar Post set deep with stones around it
 November 1978, Jerry L. Jones, #19838, recorded survey, Liber 417, Page 624
 Found Mon Box 3/4" Pipe
 Southeast to Road Sign 33.35 feet
 Southwest to Road Sign 38.65 feet
 North to Centerline 14" Twin Oak 44.7 feet
 November 1978, Jerry L. Jones #19838, LCRC, Liber 1, Page 444
 Same as above.
 November 1987, Thomas J. Mueller, #25861, recorded survey, Liber 479, Page 1245
 Found Mon Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 3/4" Iron Pipe in Mon Box 1 foot long, set in 1-1/2" iron pipe, found large stone under pipe 2.5 feet deep
 On Westside of Pipe 2.2 feet deep with small stones and broken glass
 Corner is common townships 11 and 12 North, 4 and 5 West

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Remonumentation Corner set over Pipes on East side Large Stone
 Found Nail and Tag 26" Twin Maple S30°W 73.92 feet
 Found Nail and Tag Cedar Post S50°E 42.38 feet
 Found 14" Twin Oak (now stump) North 44.83 feet
 Northeast corner brick pillar 1' square S70°W 139.77 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley
 Surveyor's Michigan License No. 30104

Date 5 Aug 94

