

**SURVEY & REMONUMENTATION COMMISSION**  
**AUG 31 1994**

**GRATIOT COUNTY REMONUMENTATION PROGRAM**

LIBER **538** PAGE **512**  
 1994

Corner approved by Peer Group on 5 Aug, 1994

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**GRATIOT CO. MICH.  
 RECORDED**

'94 AUG 19 AM 10 09

*Janet M. Davis*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Gratiot Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey Sec 7 T 11 R 4 A-5, SW Corner  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, William Tingley a field survey on July 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 May 4, 1831, GLO Notes, R. Clarke, Jr., Deputy Surveyor  
 Set Post  
 Maple 16" S24°E 49 links  
 Elm 10" N57°E 18 links  
 July 1879, S. S. Hastings, County Surveyor, Liber C, Page 33  
 Long Stone 10" x 10" x 30" with stone and crockery around it

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found large stone (12" x 12") 9" in depth with "x" on top  
 Found metal on East side (Junk & Glass)  
 Corner 50 feet +/- North of Centerline Paved Road  
 Axle shaft Corner to 12 and 13 T11N-R5W South 102.1 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set Remonumentation Corner and Mon Box over stone with "x" on top  
 Top Center concrete Right of Way Marker S35°W 91.25 feet  
 Set Nail and Tag Power Pole S70°W 27.23 feet  
 2" White Birch (No Nail) N60°W 60.55 feet  
 Axle shaft - Corner to 12 and 13, T11N-R5W 102.1 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 5 Aug, 1994  
 Surveyor's Michigan License No. 30104

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISIONS MARCH, 1993

